


**Product data sheet**  
Characteristics

**QO124L125G**  
LOAD Center QO MLO 240V 125A 1PH 24SP



**Main**

Product or component type	Load Center
Range of product	QO
Load center type	Main lugs
Line Rated Current	125 A
Number of spaces	24
Short-circuit current	65 kA
Number of circuits	24
Number of tandem circuit breakers	0
Phase	1 phase
System Voltage	120/240 V AC

**Complementary**

AWG gauge	AWG 6...AWG 2/0 (aluminium/copper)
NEMA degree of protection	NEMA 1 indoor
Cover type	Order separately
Electrical connection	Lugs
Device composition	Grounding bar included (not installed)
Electrical connection	Lugs
Wiring configuration	3-wire
Material	Tin plated copper busbar
Enclosure material	Welded sheet steel
Surface finish	Baked enamel grey
Box number	7
Product certifications	UL listed
Height	531 mm
Width	14.25 in (362 mm)

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications