


AURORA™ 12" and 8" LED Retrofit Highway Crossing Signals

Features

12" AURORA 300 and 160

- Brightest signal available in the market – 1600 cd on axis (300)
- Low cost – high intensity – 830 cd on axis (160)
- Independent bright white LED side lights for best viewing
- Regulated power supply – LED unit emits constant light output even at low voltages
- Red high impact UV stabilized outer lens
- No focusing required
- Compatible with all standard highway crossing signal housings
- Voltage turnoff at 7.5 volts
- No phankill required



AURORA™ Complete 12" LED Retrofit Signal

The **AURORA 12" LED** lamp unit measures 12" in diameter. It is a self contained unit; the lens and individual LEDs are not replaceable. The 12" LED unit is sealed and includes a high impact, UV stabilized, outer lens and separate **white sidelights**. A regulated power supply maintains constant light output during supply voltage variation.

The 12" LED units are available in a retrofit kit for installation in any standard highway crossing signal housing. These units are also available as a complete signal head with an aluminum housing, 20" background, and hood. For more information refer to manual P2468 and instruction sheet P2468-IS1.

Ordering Information

Product Name	Description	Part Number
AURORA 12" 160	12-inch AURORA Highway Crossing Signal Retrofit Kit	59649-200-02
AURORA 12" 300	Ultra Bright 12-inch AURORA Highway Crossing Signal Retrofit Kit	59649-200-03
AURORA 12" 160	12-inch AURORA Highway Crossing Signal Complete with Housing, 20-inch Dia. Background and Hood	59649-200-04
AURORA 12" 300	Ultra Bright 12-inch AURORA Highway Crossing Signal Complete with Housing, 20-inch Dia. Background and Hood	59649-200-05
AURORA 8"	8-inch AURORA Highway Crossing Signal Retrofit Kit	59649-202-02