

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						880				880		CY	COMMON EXCAVATION	203.15				
								610		610		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
						345				345		CY	SAND BORROW	203.31				
						1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								305		305		CY	STRUCTURE EXCAVATION	204.25				
								125		125		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						255				255		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						660				660		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				
						27				27		CY	AGGREGATE SURFACE COURSE	401.10				
						11				11		CWT	EMULSIFIED ASPHALT	404.65				
						1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								105		105		CY	CONCRETE, HIGH PERFORMANCE CLASS A (FPQ)	501.33				
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								125		125		LF	STEEL PILING, HP 12 X 63	505.155				
								2		2		EACH	DYNAMIC PILE LOADING TEST	505.45				
								84500		84500		LB	STRUCTURAL STEEL, PLATE GIRDER (FPQ)	506.55				
								27500		27500		LB	REINFORCING STEEL, LEVEL I	507.11				
								140		140		LF	DRILLING AND GROUTING DOWELS	507.16				
								1		1		LS	SHEAR CONNECTORS (760 - 7/8" X 7")	508.15				
								265		265		SY	LONGITUDINAL DECK GROOVING	509.10				
								25		25		GAL	WATER REPELLENT, SILANE	514.10				
								52		52		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								52		52		LF	JOINT SEALER, HOT POURED	524.11				
								196.75		196.75		LF	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	525.335				
								1		1		EACH	REMOVAL OF STRUCTURE (1267 SF - EST)	529.15				
								8		8		EACH	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	531.17				
													BEGIN OPTION AA					
								1		1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT NO. 1)	540.10				
								1		1		LS	SPECIAL PROVISION (CONTRACTOR FABRICATED PRECAST CONCRETE STRUCTURE) (ABUTMENT NO. 1)	900.645				
													END OPTION AA					
													BEGIN OPTION BB					
								1		1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT NO. 2)	540.10				
								1		1		LS	SPECIAL PROVISION (CONTRACTOR FABRICATED PRECAST CONCRETE STRUCTURE) (ABUTMENT NO. 2)	900.645				
													END OPTION BB					
													BEGIN OPTION CC					
								1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 1)	540.10				
								1		1		LS	SPECIAL PROVISION (CONTRACTOR FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB NO. 1)	900.645				
													END OPTION CC					

