

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION DD					
								1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB NO. 2)	540.10				
								1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB NO. 2)	900.645				
													END OPTION DD					
								43		43		CY	CONCRETE, CLASS C	541.30				
						1				1		MGAL	DUST CONTROL WITH WATER	609.10				
						130				130		CY	STONE FILL, TYPE I	613.10				
								315		315		CY	STONE FILL, TYPE III	613.12				
						30				30		LF	REMOVAL OF EXISTING FENCE	620.55				
						204				204		LF	BOX BEAM GUARDRAIL	621.30				
						4				4		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
						4				4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	621.725				
						280				280		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						20				20		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						400				400		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
						2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						1100				1100		LF	4 INCH YELLOWLINE	646.21				
							680			680		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							630			630		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							65			65		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							25			25		LB	SEED	651.15				
							200			200		LB	FERTILIZER	651.18				
							1			1		TON	AGRICULTURAL LIMESTONE	651.20				
							0.5			0.5		TON	HAY MULCH	651.25				
							26			26		CY	TOPSOIL	651.35				
							620			620		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN	652.10				
							65			65		HR	MONITORING EPSC PLAN	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							620			620		SY	TEMPORARY EROSION MATTING	653.20				
							35			35		CY	VEHICLE TRACKING PAD	653.35				
							230			230		LF	BARRIER FENCE	653.50				
							760			760		LF	PROJECT DEMARCATION FENCE	653.55				
						12				12		SF	TRAFFIC SIGNS, TYPE A	675.20				

