

The project quantities are as follows:

- The unit area and volume quantities are neat quantities. Contractor shall confirm the quantities and add in any additional necessary factors (i.e., waste, compaction, etc.)
- Drainage aggregate includes 12" zone behind blocks, core fill and/or voids between blocks.
- Retained zone is a 1H:1V up from the bottom back corner of the base block and includes quantity of 1" crushed stone up to 1-foot above the 100-yr HWL.

Wall	Wall Length	Block Area	Ret. Grav.	Leveling Pad	Drainage Aggregate
	(FT)	(SF)	(CY)	(CY)	(CY)
1	22.00	226.67	58.00	3.00	11.00
TOTAL:	22.00	226.67	58.00	3.00	11.00

Unit	SF/Unit	Wall 1	Area	Total Units	Total SF
T	5.33	5.00	26.67	5.00	26.67
HT	2.67	1.00	2.67	1.00	2.67
24M	5.33	13.00	69.33	13.00	69.33
2H	2.67	3.00	8.00	3.00	8.00
39M	5.33	13.00	69.33	13.00	69.33
3H	2.67	1.00	2.67	1.00	2.67
60M	5.33	5.00	26.67	5.00	26.67
6H	2.67	1.00	2.67	1.00	2.67
60B	5.33	1.00	5.33	1.00	5.33
72M	5.33	1.00	5.33	1.00	5.33
72B	5.33	1.00	5.33	1.00	5.33
7H	2.67	1.00	2.67	1.00	2.67
	TOTAL:	Wall 1	226.67	TOTAL SF	226.67

