


Reinforcing Schedule													Reinforcing Schedule														
Qty	Size	Length	Mark	Type	A	B	C	D	E	G	H	J	K	Qty	Size	Length	Mark	Type	A	B	C	D	E	G	H	J	K
38	#5	16'-10 ¹ / ₄ "	AS1501	1	8'-1 ¹ / ₂ "	8'-1 ¹ / ₂ "						7 ¹ / ₄ "		4	#5	3'-0 ¹ / ₂ "	AB1511	Str									
36	#5	11'-7 ³ / ₄ "	AS1502	1	5'-6 ¹ / ₂ "	5'-6 ¹ / ₂ "						7 ¹ / ₄ "		8	#5	20'-0"	AB1512	Str									
24	#6	19'-5 ¹ / ₂ "	AS1601	Str										6	#6	4'-3"	AB1601	14		3'-3"	1'-0"			3'-1 ¹ / ₈ "	1'-0"		
33	#8	19'-5 ¹ / ₂ "	AS1801	1	6"	19'-5 ¹ / ₂ "						8 ¹ / ₄ "		4	#6	4'-5 ³ / ₈ "	AB1602	30		3'-2 ⁷ / ₈ "	1'-0 ³ / ₄ "			3'-1"	12"		
36	#5	17'-3 ¹ / ₄ "	AS2501	1	8'-4"	8'-4"						7 ¹ / ₄ "		4	#6	6'-9"	AB1603	17		2'-3 ¹ / ₂ "	4'-5 ¹ / ₂ "						
36	#5	11'-10 ³ / ₄ "	AS2502	1	5'-7 ³ / ₄ "	5'-7 ³ / ₄ "						7 ¹ / ₄ "		4	#6	5'-4 ¹ / ₂ "	AB1604	17		2'-3 ¹ / ₂ "	3'-1"						
24	#6	19'-5"	AS2601	Str										8	#6	7'-4"	AB1605	14		2'-11"	1'-6"	2'-11"					
33	#8	20'-7 ¹ / ₂ "	AS2801	1	6"	19'-5 ¹ / ₂ "						8 ¹ / ₄ "		4	#6	4'-5 ¹ / ₂ "	AB1606	Str									
16	#5	5'-5"	WW2501	17		2'-2"	1'-1"	2'-2"						4	#6	3'-1"	AB1607	Str									
18	#5	8'-7 ³ / ₄ "	WW2502	Str										4	#6	8'-3 ¹ / ₈ "	AB1701	Str									
10	#5	7'-4 ⁷ / ₈ "	WW2503	Str										4	#7	9'-11"	AB1702	Str									
13	#6	7'-7 ⁵ / ₈ "	WW2601	Str										4	#7	20'	AB1703	Str									
10	#5		WW25UX											10	#5	5'-5"	WW1501	17		2'-2"	1'-1"	2'-2"					
13	#6		WW26UX											10	#5	7'-4 ¹ / ₂ "	WW1502	Str									
6	#5	4'-1"	CW2501	14		3'-2 ¹ / ₄ "	10 ³ / ₄ "				3'-0 ³ / ₈ "		11 ⁷ / ₈ "	8	#5	4'-2 ¹ / ₄ "	WW1503	Str									
4	#5	4'-4 ³ / ₄ "	CW2502	Str										11	#6	3'-10"	WW1601	Str									
3	#5	7'-0 ¹ / ₂ "	CW2503	17		2'-2"	2'-8 ¹ / ₂ "	2'-2"						8	#5		WW15UX										
6	#5	10'-2 ¹ / ₂ "	CW2504	T1		2'-3"	2'-6 ¹ / ₂ "	2'-3"	2'-6 ¹ / ₂ "	3 ³ / ₄ "	2'-5"		9 ³ / ₈ "	11	#6		WW16UX										
7	#6	4'-3"	CW2601	14		3'-3"	1'-0"				3'-1 ¹ / ₈ "		1'-0"	6	#5	4'-0 ³ / ₄ "	CW1501	30		3'-2 ¹ / ₈ "	10 ⁵ / ₈ "			3'-0 ¹ / ₄ "	11 ³ / ₄ "		
4	#6	4'-4"	CW2602	Str										4	#5	4'-3 ⁷ / ₈ "	CW1502	Str									
4	#6	6'-7 ¹ / ₂ "	CW2603	17		2'-3 ¹ / ₂ "	4'-4"							3	#5	7'-0 ¹ / ₂ "	CW1503	Str									
4	#5		CW25UX											6	#5	10'-2 ¹ / ₂ "	CW1504	T1		2'-3"	2'-6 ¹ / ₂ "	2'-3"	2'-6 ¹ / ₂ "	3 ³ / ₄ "	2'-5"	9 ³ / ₈ "	
8	#6		CW26UX											7	#6	4'-5 ³ / ₈ "	CW1601	30		3'-2 ⁷ / ₈ "	1'-0 ³ / ₄ "			3'-1"	12"		
3	#5	12'-11 ¹ / ₂ "	AB1501	T1		2'-7"	3'-7"	2'-7"	3'-7"	3 ³ / ₄ "				4	#6	4'-3 ¹ / ₈ "	CW1602	Str									
6	#5	12'-1 ³ / ₄ "	AB1502	T1		2'-7"	3'-2 ¹ / ₈ "	2'-7"	3'-2 ¹ / ₈ "	3 ³ / ₄ "				4	#6	6'-6 ⁵ / ₈ "	CW1603	17		2'-3 ¹ / ₂ "	4'-3 ¹ / ₈ "						
6	#5	11'-4 ¹ / ₄ "	AB1503	T1		2'-7"	2'-9 ³ / ₈ "	2'-7"	2'-9 ³ / ₈ "	3 ³ / ₄ "				4	#5		CW15UX										
5	#5	10'-6 ¹ / ₂ "	AB1504	T1		2'-7"	2'-4 ¹ / ₂ "	2'-7"	2'-4 ¹ / ₂ "	3 ³ / ₄ "				8	#6		CW16UX										
12	#5	5'-6 ⁵ / ₈ "	AB1505	Str										13	#5	4'-1"	WC3501	Str									
2	#5	16'-0 ³ / ₄ "	AB1506	Str										12	#5	3'-4"	WC3502	1	5"	1'-8"			5"		5"		
2	#5	23'-10 ³ / ₈ "	AB1507	Str										7	#5	5'-10 ⁵ / ₈ "	WC3503	17		2'-2"	1'-6 ⁵ / ₈ "	2'-2"					
5	#5	4'-1"	AB1508	14		3'-2 ¹ / ₄ "	10 ³ / ₄ "				3'-0 ³ / ₈ "		11 ⁷ / ₈ "	6	#5	5'-0 ³ / ₈ "	WC3504	14		2'-11"	2'-1 ³ / ₈ "			2'-8 ³ / ₈ "	3'-2 ¹ / ₂ "		
3	#5	4'-0 ³ / ₄ "	AB1509	30		3'-2 ¹ / ₈ "	10 ⁵ / ₈ "				3'-0 ¹ / ₄ "		11 ³ / ₄ "	6	#5	8'-10 ³ / ₈ "	WC3505	14		2'-11 ³ / ₄ "	5'-10 ⁵ / ₈ "			2'-9 ¹ / ₈ "	6'-11 ⁷ / ₈ "		
4	#5	4'-2 ¹ / ₂ "	AB1510	Str										6	#5	4'-9"	WC3506	Str									

Vermont Agency of Transportation
RECEIVED
 CK'D BY: _____ OK'D BY: Rob Young
 April 21, 2017
 RESUBMIT NO: _____ Approved AsNoted
 By: Rob Young DATE: 04/28/2017

CONTRACTORS VISPE:	LEGEND: (A) Oxford A750-7 (B) P52:20T x 10" Lift (C) 4" Pipe (D) 3" Pipe (E) Ø 24" Galv. Corrugated Steel Pipe (F) Ø 15" Galv. Corrugated Steel Pipe (G) Ø 3" x 24" Plastic Corrugated Sleeve (H) P53 Lift w/ Tension Bar (I) 1" Chamfer	PRECAST CONCRETE ABUTMENT SHOP DRAWINGS (SDI JOB #18544) SUPERVISOR: E. Barendse DETAILER: I. ADAMS CHECKER: E. Barendse ENGINEER: CONCRETE ENG. SOLUTIONS		PROJ. NAME: HUNTINGTON PROJECT #: BF 0211(32) LOCATION: HUNTINGTON, VT	INSTALLER: S.D. IRELAND CONCRETE WILLISTON, VT 05495 Ph: (802) 863-6222 04/20/17	FABRICATOR: 193 INDUSTRIAL AVE. WILLISTON, VT 05495 Ph: (802) 863-6222 REINFORCING_SCHEDULE		22/29
		04/20/17	REINFORCING_SCHEDULE	22/29				