



Casco Bay Steel Structures
 One Wallace Avenue, South Portland ME 04106
AWS - Welding Procedure Specification (WPS)
 WeldOffice WPS

WPS record number	201	Revision	1	Qualified to	AWS D1.5
Date	4/24/2014	Company name	Casco Bay Steel Structures		

JOINTS: Typical joint(s). See actual production drawings and engineering specifications for details.

	<p>3/8 single pass flat 5/16 single pass Horizontal</p> <table border="1"> <thead> <tr> <th></th> <th>Amps</th> <th>Volts</th> <th>Travel Speed</th> </tr> </thead> <tbody> <tr> <td>AVG</td> <td>604 /</td> <td>29.5 /</td> <td>17.1 IPM</td> </tr> <tr> <td>MIN</td> <td>544 /</td> <td>27.4 /</td> <td>14.5 IPM</td> </tr> <tr> <td>MAX</td> <td>644 /</td> <td>31.6 /</td> <td>19.7 IPM</td> </tr> </tbody> </table>		Amps	Volts	Travel Speed	AVG	604 /	29.5 /	17.1 IPM	MIN	544 /	27.4 /	14.5 IPM	MAX	644 /	31.6 /	19.7 IPM
	Amps	Volts	Travel Speed														
AVG	604 /	29.5 /	17.1 IPM														
MIN	544 /	27.4 /	14.5 IPM														
MAX	644 /	31.6 /	19.7 IPM														
<p>* Multiple passes may be used if drawing details call for a larger size fillet weld than noted above in the position welding is being performed</p>																	

Type of groove	Fillet weld	Minimum groove angle	(deg.)	N/A
		Minimum root opening	(in.)	N/A
		Maximum root face	(in.)	N/A

PREHEAT TABLE

Applicable standard	
AWS D1.5 Bridge Welding Code	For thickness 1/8 to 3/4(in.): 50(*F). Preheat to 70(*F) if the base metal temperature is below 32(*F). Over 3/4 thru 1-1/2(in.): 70(*F). Over 1-1/2 thru 2-1/2(in.): 150(*F). Over 2-1/2(in.): 225(*F). Refer to AWS D1.5 2010 Table 4.3 (pg 85)
AWS D1.5 2010 FCM	For thickness 1/8 to 3/4(in.): 100(*F). Over 3/4 thru 1-1/2(in.): 200(*F). Over 1-1/2 thru 2-1/2(in.): 300(*F). Over 2-1/2(in.): 350(*F). No welding to be done if ambient temperature in immediate area is below 0(*F)
New York SCM	Up to 3/4 -----100 (F) Over 3/4 to 1-1/2 -----200 (F) Over 1-1/2 to 2-1/2 -----300 (F) Over 2-1/2 -----350 (F)

TECHNIQUE

Supplementary MF control	
Peening	
Surface preparation	Grind/Blast/chemical/wirebrush clean to be free of moisture, slag, millscale, oils, dust
Initial/interpass cleaning	Brushing and Grinding
Back gouging method	None

NOTES

AWS FCM preheats are taken from AWS D1.5 2010 Clause 12 Table 12.4 and are based upon calculated heat input calculated in accordance with section 5.12 with an as welded H8 designation for the electrode combination we are using. This higher preheat will be used on non weathering steels also.

Vermont Agency of Transportation
RECEIVED

CK'D BY RSY OK'D BY WDL

March 9, 2016

RESUBMIT No Approved
 BY RSY DATE 05/26/2016

Signature 1		Signature 2	
Name	Signature	Name	Signature
Matthew Cote			
Date		Date	
6/2/2014			
Signature 3		Signature 4	
Name	Signature	Name	Signature
Date		Date	