

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL OR UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS		NO. OF NEW POSTS	SQUARE STEEL			TUBULAR STEEL					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM		SALVAGE TO	REMOVE	R E T A I N	R E M O V E	1.75	2.00	2.50	3.00			3.50	4.00	5.00
WB	MM 2.918 LT	H	R1-1	30	30			6.25			X	1	15									REPLACE EXISTING STOP SIGN AND POST LOCATED 21' WEST OF POLE # 17	X		
WB	MM 2.922 LT	G	VR-017	24	30						X											REMOVE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED ADJACENT TO POLE # 17			
WB	MM 2.996 LT	H	R1-1	30	30			6.25			X	1	15									REPLACE EXISTING STOP SIGN AND POST LOCATED 48' WEST OF POLE # 8/63	X		
WB	MM 2.998 LT	G	VR-017	24	30						X											REMOVE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED 37' WEST OF POLE # 8/63			
EB	MM 3.611 RT	A	R2-5C	24	30						X											REMOVE EXISTING SPEED ZONE AHEAD SIGN AND POST LOCATED ACROSS FROM POLE # 76			
EB	MM 3.676 RT	A	W3-5	36	36			9.00				2	30									INSTALL A NEW 35 MPH AHEAD SIGN ON TWO NEW POSTS LOCATED 37' WEST OF AND ACROSS FROM POLE # 132	X		
EB	MM 3.806 RT	A	R2-1	24	30			5.00			X	1	15									REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 5' WEST OF AND ACROSS FROM POLE # 6/128	X		
WB	MM 3.806 LT	F	R2-1	24	30			5.00				1	15									INSTALL NEW SPEED LIMIT SIGN AND POST LOCATED 5' WEST OF POLE # 6/128	X		
WB	MM 3.809 LT	F	R2-1	24	30						X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 11' EAST OF POLE # 6/128			
EB	MM 3.985 RT	A	W1-2L	30	30			6.25				1	15									INSTALL NEW CURVE LEFT SIGN AND POST LOCATED 143' WEST OF AND ACROSS FROM POLE # NET/122/12 (MM 4.012)	X		
EB	MM 4.005 RT - MM 4.073 RT	A B		6	8		(14) TYPE 11 6"X 8" WHITE DELINEATORS															INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60 FT APART ON 7 POSTS. INSTALL FIRST 37' WEST OF AND ACROSS FROM POLE # NET/122/12 (MM 4.012 LT)	4		
WB	MM 4.068 LT	F	D3-1	36	12			3.00			X	1	15									REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 11' WEST OF AND ACROSS FROM POLE # NET/122/12 (MM 4.070 RT)		12	
WB	MM 4.100 LT	F	W1-2R	30	30			6.25				1	15									INSTALL NEW CURVE RIGHT SIGN AND POST LOCATED 42' WEST OF AND ACROSS FROM POLE # NET/15	X		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(16)
FILE NAME: lunenburg-traffic-signs/summary6.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
LUNENBURG TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 12/30/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 23 OF 50