STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

BRISTOL
MONKTON ROAD
& HARDSCRABBLE ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.482 LT	F	VD-062	72	16		Wallace Realty on mtn terrace					X														INSTALL THE OBDS SIGN AND POSTS FROM MM 0.443 LT BENEATH THE NEW OBDS SIGN FROM THE SAME POINT. LOCATED 190' NORTH OF AND ACROSS FROM POLE # 39X/SI.			
							HARDSCRABBLE ROAD																						
WB	MM 0.009 RT	A	R1-1	30	30		STOP	6.25								1		15								INSTALL A NEW STOP SIGN AND POST LOCATED 48' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD	X		
EB	MM 0.009 LT	F	R1-1	30	30		STOP	6.25					X		X	1		15								REPLACE EXISTING STOP SIGN AND POST LOCATED 48' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD	X		
EB	MM 0.009 LT	H G	D3-1	60	12		Hardscrabble Rd	5.00								2		30								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 48' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD		14	
WB	MM 0.043 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 227' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD	X		
WB	MM 0.043 RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X													REMOVE EXISTING LEGAL LOAD LIMIT SIGN LOCATED 227' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD			
EB	MM 0.075 LT	F	W3-1	30	30		STOP AHEAD						X		X											REMOVE EXISTING STOP AHEAD SIGN AND POST LOCATED 396' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD			
EB	MM 0.075 LT	F	W3-1	30	30			6.25								1		15								INSTALL A NEW STOP AHEAD SIGN AND POST LOCATED 396' WEST OF THE INTERSECTION OF HARDSCRABBLE RD AND MONKTON RD	X		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

				EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB									
						1	4		3			90															
		SF	SF	EA				EA		EA	FT			EA	LB													
		28.75		5				3		6	90																	

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: bristoltrafficsign5.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
BRISTOL TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 21 OF 73