STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

BRISTOL
RIVER ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.002 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		15								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 264' WEST OF POLE # X29	X		
EB	MM 0.029 RT						SIGN POST								X											REMOVE EXISTING SIGN POST LOCATED 121' WEST OF POLE # X29			
EB	MM 0.073 RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 111' EAST OF POLE # X29			
EB	MM 0.152 RT	A	W1-3R	30	30			6.25								1		15								INSTALL A NEW REVERSE TURN RIGHT SIGN AND POST LOCATED 42' EAST OF AND ACROSS FROM DRIVEWAY # 308	X		
EB	MM 0.152 RT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-3R SIGN LOCATED 42' EAST OF AND ACROSS FROM DRIVEWAY # 308	X		
EB	MM 0.256 RT	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						X		X											REMOVE EXISTING SCHOOL BUS STOP AHEAD SIGN AND POST LOCATED 232' WEST OF MAILBOX # 63			
EB	MM 0.256 RT	A	S3-1	30	30	FYG		6.25								1		15								INSTALL A NEW SCHOOL BUS STOP AHEAD SIGN AND POST LOCATED 232' WEST OF MAILBOX # 63	X		
EB	MM 0.256 RT	A B	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 185' WEST OF MAILBOX # 63	X		
EB	MM 0.290 RT	A B	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 53' WEST OF MAILBOX # 63	X		
WB	MM 0.300 LT	F	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1		15								INSTALL A NEW HIDDEN DRIVE RIGHT SIGN AND POST LOCATED ACROSS FROM MAILBOX # 63		13	
EB	MM 0.309 RT	A B	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 48' EAST OF MAILBOX # 63	X		
EB	MM 0.330 RT	A B	W1-8L W1-8R	18 18	24 24		B-B	3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 158' EAST OF MAILBOX # 63	X		
								SF 50	SF	EA 2	EA	EA	EA 2	EA	EA 3	EA 8	FT	FT 120	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: bristolrivertrafficsign1.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
BRISTOL(RIVER ROAD)
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 23 OF 73