

TRAFFIC SIGN SUMMARY SHEET

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	REPLACE		REPLACE	REPLACE	1.75	2.00	2.50	FOUNDATION	3.00			3.50	4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
SB	MM 0.837 LT	F	R2-1	24	30			5.00							1		15							INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # NET/38/2A	X					
NB	MM 0.865 RT	C	R1-1	30	30																			REMOVE EXISTING STOP SIGN AND POST LOCATED 21' SOUTH OF POLE # 943/3/SOLID/13/38						
NB	MM 0.866 RT	C	W1-7	48	24			8.00							2		30							REPLACE EXISTING LARGE DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 16' SOUTH OF POLE # 943/3/SOLID/13/38	X					
NB	MM 0.871 RT	F E	D3-1	42	12																			REMOVE EXISTING STREET NAME SIGN AND POST LOCATED 11' NORTH OF POLE # 943/3/SOLID/13/38						
NB	MM 0.871 RT	A B	D3-1	60	12																			REMOVE EXISTING STREET NAME SIGN LOCATED 11' NORTH OF POLE # 943/3/SOLID/13/38						
SB	MM 0.919 LT	F	W2-2R	30	30			6.25							1		15							INSTALL A NEW SIDE ROAD RIGHT SIGN AND POST LOCATED 264' NORTH OF AND ACROSS FROM POLE # 943/3/SOLID/13/38	X					
SB	MM 0.919 LT	F	W16-8P	36	8			2.00																INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2R SIGN LOCATED 264' NORTH OF AND ACROSS FROM POLE # 943/3/SOLID/13/38			16			
NB	MM 0.919 RT	A	R2-1	24	30			5.00							1		15							REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 264' NORTH OF POLE # 943/3/SOLID/13/38	X					
NB	MM 0.976 RT	A	VW-060	30	30																			REMOVE EXISTING HIDDEN DRIVES SIGN AND POST LOCATED 79' SOUTH OF POLE # 40T/5/15T						
NB	MM 1.035 RT	A	VW-060	30	30			6.25							1		15							INSTALL A NEW HIDDEN DRIVES SIGN AND POST LOCATED 232' NORTH OF POLE # 40T/5/15T			13			
SB	MM 1.183 LT	F	VW-060	30	30			6.25							1		15							INSTALL A NEW HIDDEN DRIVES SIGN AND POST LOCATED 391' SOUTH OF POLE # 9/31			13			
NB	MM 1.227 RT	A	S3-1	30	30																			REMOVE EXISTING SCHOOL BUS STOP AHEAD SIGN AND POST LOCATED 158' SOUTH OF AND ACROSS FROM POLE # 9/31						
NB	MM 1.227 RT	A	VW-060	30	30																			REMOVE EXISTING HIDDEN ENTRANCE SIGN BENEATH THE EXISTING S3-1 LOCATED 158' SOUTH OF AND ACROSS FROM POLE # 9/31						
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".										EA	EA	EA	EA	EA	EA	8	6	FT	FT	FT	LB	LB	LB	LB						
								SF	SF	EA	EA	EA	EA	EA	EA	8	6	7	FT	FT	EA	LB								
								38.75		8								105												

PROJECT NAME: STATEWIDE NORTHWEST REGION
 PROJECT NUMBER: STP HRRR(17)
 FILE NAME: georgiatrafficsign2.dgn
 PROJECT LEADER: J. DEVLIN
 DESIGNED BY: N. PATTIS
 GEORGIA TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 1/22/2014
 DRAWN BY: N. PATTIS
 CHECKED BY: B. GROSE
 SHEET 27 OF 73