STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

GEORGIA
BALLARD ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.257 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		15								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # 9/31	X		
NB	MM 1.288 RT	A	VW-060	30	30		HIDDEN DRIVES	6.25								1		15								INSTALL A NEW HIDDEN DRIVES SIGN AND POST LOCATED 16' SOUTH OF AND ACROSS FROM POLE # 30½		13	
NB	MM 1.288 RT	A	VW-205	30	30		WATCH FOR TURNING VEHICLES	6.25																		INSTALL A NEW WATCH FOR TURNING VEHICLES SIGN BENEATH THE NEW VW-060 SIGN LOCATED 16' SOUTH OF AND ACROSS FROM POLE # 30½		13	
SB	MM 1.537 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 1257' SOUTH OF POLE # 10T/18	X		
NB	MM 1.775 RT	A	W11-5	30	30			6.25								1		15								INSTALL A NEW TRACTOR SYMBOL SIGN AND POST LOCATED ACROSS FROM POLE # 10T/18	X		
NB	MM 1.868 RT	A	VW-060	30	30		HIDDEN DRIVES	6.25								1		15								INSTALL A NEW HIDDEN DRIVES SIGN AND POST LOCATED 111' SOUTH OF AND ACROSS FROM POLE # 20/20		13	
NB	MM 1.982 RT	A	W2-2L	30	30			6.25								1		15								INSTALL A NEW SIDE ROAD LEFT SIGN AND POST LOCATED ACROSS FROM POLE # SOLID/94/22	X		
NB	MM 1.982 RT	A	W16-8P	26	8		Sodom Rd	1.44																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2L SIGN LOCATED ACROSS FROM POLE # SOLID/94/22		16	
NB	MM 2.021 RT	C	W1-7	48	24			8.00								2		30								INSTALL A NEW LARGE DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 48' SOUTH OF AND ACROSS FROM POLE # 943/23/117/13/17	X		
SB	MM 2.068 LT	F	W2-2R	30	30			6.25								1		15								INSTALL A NEW SIDE ROAD RIGHT SIGN AND POST LOCATED 58' SOUTH OF POLE # SOLID/161/2/23X	X		
SB	MM 2.068 LT	F	W16-8P	26	8		Sodom Rd	1.44																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2R SIGN LOCATED 58' SOUTH OF POLE # SOLID/161/2/23X		16	
NB	MM 2.750 RT	A	M2-1	21	15		JCT	2.19								1		15								INSTALL A NEW JUNCTION SIGN AND POST LOCATED 16' SOUTH OF AND ACROSS FROM POLE # 943/35-2/NET/199 ¼			E-136A
NB	MM 2.750 RT	A	M1-4	24	24		7	4.00																		INSTALL A NEW US ROUTE MARKER SIGN BENEATH THE NEW M2-1 SIGN LOCATED 16' SOUTH OF AND ACROSS FROM POLE # 943/35-2/NET/199¼			E-136A
SB	MM 2.760 LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 37' NORTH OF POLE # 943/35-2/NET/199 ¼			
								SF 64.57	SF	EA 2			EA 2	EA 2	EA 2	EA 10	FT 150			EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: georgiatrafficsign3.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
GEORGIA TRAFFIC SIGN SUMMARY SHEET 3
PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE