STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MILTON
DUFFY ROAD
& ROLLIN IRISH ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							DUFFY ROAD																						
SB	MM 0.017 RT	A	W2-2L	30	30			6.25								1		15								INSTALL NEW SIDE ROAD LEFT SIGN AND POST LOCATED 58' NORTH OF POLE # 5/55	X		
SB	MM 0.017 RT	A	W16-8P	36	8			2.00																		INSTALL NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2L SIGN LOCATED 58' NORTH OF POLE # 5/55		16	
NB	MM 0.053 LT	F	R2-1	24	30			5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 26' NORTH OF POLE # 406/4/56	X		
SB	MM 0.130 RT	A	R2-1	24	30			5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 380' SOUTH OF POLE # 406/4/56	X		
NB	MM 0.144 LT	F	W2-2R	30	30			6.25								1		15								INSTALL NEW SIDE ROAD RIGHT SIGN AND POST LOCATED 454' SOUTH OF AND OPPOSITE POLE # 406/4/56	X		
NB	MM 0.144 LT	F	W16-8P	36	8			2.00																		INSTALL NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2R SIGN LOCATED 454' SOUTH OF AND OPPOSITE POLE # 406/4/56		16	
							ROLLIN IRISH ROAD																						
WB	MM 0.004 CTR	K	R1-1	30	30			6.25					X		X	1		15								REPLACE EXISTING STOP SIGN AND POST LOCATED 866' WEST OF POLE # 4/115-1/62A	X		
WB	MM 0.004 CTR	K J	D3-1	30	12			2.50																		INSTALL A NEW STREET NAME SIGN ABOVE AND ON THE SAME POST AS THE NEW R1-1 SIGN LOCATED 866' WEST OF POLE # 4/115-1/62A		14	
WB	MM 0.004 CTR	L L	D3-1	54	12			4.50								2		30								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 866' WEST OF POLE # 4/115-1/62A		15	
WB	MM 0.004 LT	F	R1-1	30	30			6.25								1		15								INSTALL A NEW STOP SIGN AND POST LOCATED 866' WEST AND OPPOSITE POLE # 4/115-1/62A	X		
EB	MM 0.025 RT	A	R2-1	24	30			5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 755' WEST OF POLE # 4/115-1/62A	X		
WB	MM 0.048 LT	F E	W1-8L W1-8R	18	24			3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET LOCATED 634' WEST OF AND ACROSS FROM POLE # 4/115-1/62A	X		
WB	MM 0.067 LT	F E	W1-8L W1-8R	18	24			3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET LOCATED 533' WEST OF AND ACROSS FROM POLE # 4/115-1/62A	X		
										EA	EA	EA	EA 4	EA	EA 4		FT	FT 165	FT		LB	LB	LB	LB					
								SF 63.00	SF	EA 4				EA 4		EA 11	FT 165			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: miltontrafficsign1.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
MILTON TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 34 OF 73