STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILTON
ROLLIN IRISH ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.083 LT	F E	W1-8L W1-8R	18	24			3.00 3.00								1		15								INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET LOCATED 449' WEST OF AND ACROSS FROM POLE # 4/115-1/62A	X		
WB	MM 0.118 LT	F	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 264' WEST OF AND ACROSS FROM POLE # 4/115-1/62A	X		
WB	MM 0.118 LT	F	W13-1P	18	18			2.25																		INSTALL NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L LOCATED 264' WEST AND ACROSS FROM POLE # 4/115-1/62A	X		
WB	MM 0.761 LT	F	R2-1	24	30			5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 11' EAST OF MAILBOX # 152	X		
EB	MM 0.851 RT	A	W1-2L	30	30								X		X											REMOVE EXISTING CURVE LEFT SIGN AND POST LOCATED 407' EAST OF POLE # 131			
EB	MM 0.851 RT	A	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 407' EAST OF POLE # 131	X		
EB	MM 0.851 RT	A	W13-1P	18	18			2.25																		INSTALL NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L LOCATED 407' EAST OF POLE # 131	X		
EB	MM 0.855 RT TO MM 0.923 RT	A		6	8		(16) TYPE II - 6" X 8" WHITE DELINEATORS	5.33																		INSTALL NEW DELINEATORS (16) BACK-TO-BACK 50 FEET APART ON 8 POSTS, INSTALL FIRST 428' EAST OF POLE # 131		4	
WB	MM 0.936 LT	F	W1-1R	30	30			6.25								1		15								INSTALL NEW TURN RIGHT SIGN AND POST LOCATED 148' WEST OF MAILBOX # 196	X		
WB	MM 0.936 LT	F	W13-1P	18	18			2.25																		INSTALL NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1R LOCATED 148' WEST OF MAILBOX # 196	X		
WB	MM 0.963 LT	F	W1-2R	30	30								X		X											REMOVE EXISTING CURVE RIGHT SIGN AND POST LOCATED 5' WEST OF MAILBOX # 196			
EB	MM 0.963 RT	A	W1-3L	30	30			6.25								1		15								INSTALL A NEW REVERSE TURN LEFT SIGN AND POST LOCATED 5' WEST OF AND ACROSS FROM MAILBOX # 196	X		
EB	MM 0.963 RT	A	W13-1P	18	18			2.25																		INSTALL NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-3L LOCATED 5' WEST OF AND ACROSS FROM MAILBOX # 196	X		
								SF 50.33	SF	EA 3			EA 3		EA 3	EA 6	FT 90			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: miltontrafficsign2.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
MILTON TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 35 OF 73