STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

MORETOWN
MORETOWN MOUNTAIN ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							MORETOWN MOUNTAIN ROAD																						
EB	MM 0.007 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED 79' WEST OF AND ACROSS FROM POLE # GMP/1			
EB	MM 0.008 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED 74' WEST OF AND ACROSS FROM POLE # GMP/1			
EB	MM 0.009 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED 69' WEST OF AND ACROSS FROM POLE # GMP/1			
WB	MM 0.014 LT	F	R1-1	30	30		STOP	6.25								1		15								INSTALL A NEW STOP SIGN AND POST LOCATED 42' WEST OF POLE # GMP/1	X		
WB	MM 0.015 LT	F	R1-1	30	30		STOP						X		X												REMOVE EXISTING STOP SIGN AND POST LOCATED 37' WEST OF POLE # GMP/1			
EB	MM 0.016 RT	A	R2-1	24	30		SPEED LIMIT 35	6.25					X		X	1		15									REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 32' WEST OF AND ACROSS FROM POLE # GMP/1	X		
EB	MM 0.016 RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	6.25								1		15								INSTALL A NEW LEGAL LOAD LIMIT SIGN ABOVE AND ON THE SAME POST AS THE NEW R2-1 SIGN LOCATED 32' WEST OF POLE # GMP/1		13	
EB	MM 0.022 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED ACROSS FROM POLE # GMP/1			
EB	MM 0.023 RT	A	R2-1	24	30		SPEED LIMIT 35						X		X												REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 5' EAST OF AND ACROSS FROM POLE # GMP/1			
EB	MM 0.059 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED ACROSS FROM POLE # GMP/2			
WB	MM 0.061 LT	F	W3-1	30	30			6.25								1		15								INSTALL A NEW STOP AHEAD SIGN AND POST LOCATED 10' EAST OF POLE # GMP/2	X		
EB	MM 0.065 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED 32' EAST OF AND ACROSS FROM POLE # GMP/2			
EB	MM 0.073 RT	A	W2-3L	30	30			6.25								1		15								INSTALL A NEW SIDE ROAD LEFT UP SIGN AND POST LOCATED ACROSS FROM POLE # GMP/3	X		
EB	MM 0.073 RT	A	W16-8P	30	15		Moretown Common Rd	2.08																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-3L SIGN LOCATED ACROSS FROM POLE # GMP/3		16	
								SF 33.33	SF	EA 3	EA	EA	EA 3	EA 9	EA	EA 5	FT	FT 75	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: moretowntrafficsign.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
MORETOWN TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE