STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MORETOWN
MORETOWN MOUNTAIN ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.137 RT						I BEAM POST								X												REMOVE EXISTING I BEAM POST LOCATED 338' EAST OF AND ACROSS FROM POLE # GMP/3			
WB	MM 0.140 LT	E	D1-1	72	12		Northfield 9 ➔	6.00								2		30									INSTALL A NEW D-BOARD SIGN ON TWO NEW POSTS LOCATED 354' EAST OF POLE # GMP/3		16	
EB	MM 0.209 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																			INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 63' WEST OF AND ACROSS FROM MAILBOX # 255		4	
EB	MM 0.232 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																			INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 58' EAST OF AND ACROSS FROM MAIL BOX # 255		4	
EB	MM 0.263 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																			INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 74' WEST OF AND ACROSS FROM POLE # GMP/2/6-2		4	
EB	MM 0.312 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																			INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED ACROSS FROM MAILBOX # 331		4	
EB	MM 0.350 RT - MM 0.395 RT	A B		6	8		(10) TYPE II - 6" X 8" WHITE DELINEATORS	3.33																			INSTALL NEW DELINATORS (10) BACK-TO-BACK 60 FT APART ON 5 POSTS. LOCATE THE FIRST ONE 201' EAST OF AND ACROSS FROM MAILBOX # 331		4	
EB	MM 0.551 RT	A	W1-3L	30	30			6.25								1		15									INSTALL A NEW REVERSE TURN LEFT SIGN AND POST LOCATED 248' WEST OF AND ACROSS FROM MAILBOX # 647	X		
EB	MM 0.551 RT	A	W13-1P	18	18			2.25																			INSTALL NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-3L LOCATED 248' WEST OF AND ACROSS FORM MAILBOX # 647	X		
EB	MM 0.584 RT	A	W1-3L	30	30								X		X												REMOVE EXISTING REVERSE TURN LEFT SIGN AND POST LOCATED 74' WEST OF AND ACROSS FROM MAILBOX # 647			
EB	MM 0.588 RT	A	W1-6L	48	24			8.00								2		30									INSTALL A NEW LARGE LEFT ARROW SIGN ON TWO POSTS LOCATED 74' WEST OF AND ACROSS FROM MAILBOX # 647	X		
EB	MM 0.590 RT	B	W1-6R	48	24			8.00								2		30									INSTALL A NEW LARGE RIGHT ARROW SIGN ON TWO POSTS LOCATED 42' WEST OF AND ACROSS FROM MAILBOX # 647	X		
WB	MM 0.654 LT	E	W1-6R	48	24			8.00								2		30									INSTALL A NEW LARGE RIGHT ARROW SIGN ON TWO POSTS LOCATED 296' EAST OF MAILBOX # 647	X		
WB	MM 0.660 LT	F	W1-6L	48	24			8.00								2		30									INSTALL A NEW LARGE LEFT ARROW SIGN ON TWO POSTS LOCATED 327' EAST OF MAILBOX # 647	X		
WB	MM 0.693 LT	F	W1-5R	30	30								X		X												REMOVE EXISTING WINDING ROAD SIGN AND POST LOCATED 502' EAST OF MAILBOX # 647			
								SF 52.51	SF	EA 2				EA 3		EA 11	FT 165			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: moretowntrafficsign2.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
MORETOWN TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 39 OF 73