

# TRAFFIC SIGN SUMMARY SHEET

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL											
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	REMAIN		REPLACE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER							
																														lb/ft	lb/ft	lb/ft	lb/ft			
WB	MM 2.328 LT	F	W7-1	30	30			6.25															INSTALL A NEW HILL SIGN AND POST LOCATED ACROSS FROM POLE # CO-0P/5	X												
EB	MM 2.348 RT	A	R2-1	24	30			5.00						X		X							REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 106' EAST OF POLE # CO-0P/5	X												
EB	MM 2.408 RT	A	W7-1	30	30			6.25															INSTALL A NEW HILL SIGN AND POST LOCATED 174' WEST OF POLE # WASH ELEC/65	X												
EB	MM 2.524 RT	A	W1-2R	30	30			6.25															INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 243' WEST OF AND ACROSS FROM POLE # M0220K/F16580	X												
WB	MM 2.575 LT	F	W1-6L	48	24			8.00															INSTALL NEW LARGE RIGHT ARROW SIGN ON TWO POSTS LOCATED 26' EAST OF POLE # M0220K/F16580	X												
WB	MM 2.575 LT	E	W1-6R	48	24			8.00															INSTALL A NEW LARGE LEFT ARROW SIGN ON TWO POSTS LOCATED 26' EAST OF POLE # M0220K/F16580	X												
WB	MM 2.618 LT	F	W1-2L	30	30			6.25															INSTALL A NEW CURVE LEFT SIGN AND POST LOCATED 253' EAST OF POLE # M0220K/F16580	X												
EB	MM 2.796 RT	A	W1-2R	30	30			6.25															INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 428' WEST OF AND ACROSS FROM POLE # WASH-ELEC/72	X												
EB	MM 3.818 RT	D	R1-1	30	30			6.25															INSTALL A NEW STOP SIGN AND POST LOCATED 16' EAST OF THE INTERSECTION OF DEVIL'S WASHBOWL ROAD	X												
EB	MM 3.819 RT	A B	D3-1	72	12		<b>Devils Washbowl Rd</b>	6.00															INSTALL A NEW STREET NAME SIGN ON TWO POSTS LOCATED 16' EAST OF THE INTERSECTION OF DEVIL'S WASHBOWL ROAD			14										
EB	MM 3.826 RT	A	R2-1	24	30			5.00						X		X							REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 58' EAST OF THE INTERSECTION OF DEVIL'S WASHBOWL ROAD	X												
EB	MM 4.208 RT	A	W1-2L	30	30			6.25															INSTALL A NEW CURVE LEFT SIGN AND POST LOCATED 106' EAST OF POLE # 11/63/R19	X												
EB	MM 4.224 RT	F E	W1-8	18	24			3.00 3.00															INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET LOCATED 100' WEST OF POLE # WASH-ELEC/941	X												
EB	MM 4.258 RT	F E	W1-8	18	24			3.00 3.00															INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET LOCATED 79' EAST OF POLE # WASH ELEC/941	X												
EB	MM 4.291 RT	F E	W1-8	18	24			3.00 3.00															INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET LOCATED 63' EAST OF AND OPPOSITE POLE # 114/WASHELEC/63/R21	X												
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>																																				
								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA				
								93.75		2																										