STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

RICHMOND
WES WHITE HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 1.213 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE THE EXISTING SPEED LIMIT SIGN AND POST LOCATED 100' SOUTH OF AND ACROSS FROM MAILBOX # 1849	X		
SB	MM 1.214 LT - MM 1.248 LT	E F		6	8		(8) TYPE II - 6"X 8" WHITE DELINEATORS	2.66																		INSTALL NEW DELINEATORS (8) BACK-TO-BACK 60 FEET APART ON 4 POSTS, INSTALL THE FIRST ONE 95' SOUTH OF AND ACROSS FROM MAILBOX # 1849		4	
NB	MM 1.337 RT	A	W1-1R	30	30			6.25								1		15								INSTALL A NEW TURN RIGHT SIGN AND POST LOCATED 53' SOUTH OF MAILBOX # 1747	X		
NB	MM 1.337 RT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1R SIGN LOCATED 53' SOUTH OF MAILBOX # 1747	X		
SB	MM 1.347 LT - MM 1.493 LT	E F		6	8		(30) TYPE II 6"X 8" WHITE DELINEATORS	10.00																		INSTALL NEW DELINEATORS (30) BACK-TO-BACK 55 FEET APART ON 15 POSTS, INSTALL FIRST ACROSS FROM MAILBOX # 1747		4	
SB	MM 1.471 LT	F	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 655' NORTH OF AND ACROSS FROM MAILBOX # 1747	X		
SB	MM 1.471 LT	F	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L SIGN LOCATED 655' NORTH OF AND ACROSS FROM MAILBOX # 1747	X		
SB	MM 1.603 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 581' SOUTH OF AND ACROSS FROM MAILBOX # 1376	X		
NB	MM 1.623 RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 475' SOUTH OF MAILBOX # 1376			
NB	MM 1.623 RT	A	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 475' SOUTH OF MAILBOX # 1376	X		
NB	MM 1.623 RT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L SIGN LOCATED 475' SOUTH OF MAILBOX # 1376	X		
										EA	EA	EA	EA 3	EA	EA 3		FT	FT 75	FT		LB	LB	LB	LB					
								SF 48.16	SF	EA 3				EA 3		EA 5	FT 75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: richmondtrafficsign3.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
RICHMOND TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 51 OF 73