STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

RICHMOND
WES WHITE HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.623 RT - MM 1.680 RT	A B		6	8		(12) TYPE II - 6"X 8" WHITE DELINEATORS	4.00																		INSTALL NEW DELINEATORS (12) BACK-TO-BACK 60 FT APART ON 6 POSTS, INSTALL THE FIRST ONE 475' SOUTH OF MAILBOX # 1376		4	
SB	MM 1.705 LT	F	W1-1R	30	30			6.25								1		15								INSTALL A NEW TURN RIGHT SIGN AND POST LOCATED 42' SOUTH OF AND ACROSS FROM MAILBOX # 1376	X		
SB	MM 1.705 LT	F	W13-1P	18	18			2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1R SIGN LOCATED 42' SOUTH OF AND OPPOSITE MAILBOX # 1376	X		
SB	MM 1.763 LT	E F	D3-1	54	12		Stonefence Rd			X				X												RETAIN EXISTING STREET NAME SIGN AND POST LOCATED 211' SOUTH OF AND ACROSS FROM POLE # CTC/28			
NB	MM 2.124 RT	A	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 327' SOUTH OF MAILBOX # 909	X		
NB	MM 2.124 RT	A	W13-1P	18	18			2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L SIGN LOCATED 327' SOUTH OF MAILBOX # 909	X		
SB	MM 2.124 LT	F	R2-1	24	30			5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 327' SOUTH OF AND ACROSS FROM MAILBOX # 909	X		
NB	MM 2.138 RT	A B		6	8		(14) TYPE II 6"X 8" WHITE DELINEATORS	4.66																		INSTALL NEW DELINEATORS (14) BACK-TO-BACK AT 55 FEET APART ON 7 NEW POSTS, INSTALL THE FIRST ONE 253' SOUTH OF MAILBOX # 909		4	
NB	MM 2.156 RT	A	R2-1	24	30			5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 158' SOUTH OF MAILBOX # 909	X		
NB	MM 2.188 RT	A	W2-1	30	30			6.25								1		15								INSTALL A NEW CROSSROADS SIGN AND POST LOCATED 11' NORTH OF MAILBOX # 909	X		
SB	MM 2.206 LT	F	W1-1R	30	30			6.25								1		15								INSTALL A NEW TURN RIGHT SIGN AND POST LOCATED 106' NORTH OF AND ACROSS FROM MAILBOX # 909	X		
SB	MM 2.206 LT	F	W13-1P	18	18			2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1R SIGN LOCATED 106' NORTH OF AND ACROSS FROM MAILBOX # 909	X		
SB	MM 2.243 LT	E F	D3-1	54	12		Stonefence Rd			X				X												RETAIN EXISTING STREET NAME SIGN AND POST LOCATED 301' NORTH OF AND ACROSS FROM MAILBOX # 909			
NB	MM 2.247 RT	A B	D3-1	60	12		Robbins Mtn Rd			X				X												RETAIN EXISTING STREET NAME SIGN AND POST LOCATED 322' NORTH OF MAILBOX # 909			
										EA 3	EA	EA	EA 2	EA 3	EA 2		FT	FT 90	FT		LB	LB	LB	LB				
								SF 50.41	SF	EA 5				EA 5		EA 6	FT 90			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: richmondtrafficsign4.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
RICHMOND TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 52 OF 73