STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

STOWE
WEEKS HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							WEEKS HILL ROAD																						
SB	MM 0.002 LT	G H	D3-1	48	12		Weeks Hill Rd	4.00					X		X	2		30								REPLACE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 11' NORTH OF THE INTERSECTION OF VT ROUTE 108		15	
NB	MM 0.015 RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X		X	1		15								REPLACE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED 79' NORTH OF THE INTERSECTION OF VT ROUTE 108		13	
NB	MM 0.015 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00																		INSTALL A NEW SPEED LIMIT SIGN BENEATH THE VR-017 SIGN LOCATED 79' NORTH OF THE INTERSECTION OF VT ROUTE 108	X		
SB	MM 0.031 LT	F	M3-3	24	12		SOUTH	2.00					X		X	1		15								REPLACE EXISTING CARDINAL DIRECTION SIGN AND POST LOCATED 137' SOUTH OF POLE # 2/4-2/1			E-136B
SB	MM 0.031 LT	F	M1-5	30	24		VERMONT 108	5.00					X													REPLACE EXISTING STATE ROUTE SIGN BENEATH THE M3-3 SIGN LOCATED 137' SOUTH OF POLE # 2/4-2/1			E-136B
SB	MM 0.031 LT	F	M6-1L	21	15		←	2.19					X													REPLACE EXISTING DIRECTIONAL ARROW SIGN BENEATH THE M1-5 SIGN LOCATED 137' SOUTH OF POLE # 2/4-2/1			E-136B
SB	MM 0.031 LT	F	M3-1	24	12		NORTH	2.00					X		X	1		15								REPLACE EXISTING CARDINAL DIRECTION SIGN AND POST LOCATED 137' SOUTH OF POLE # 2/4-2/1			E-136B
SB	MM 0.031 LT	F	M1-5	30	24		VERMONT 108	5.00					X													REPLACE EXISTING STATE ROUTE SIGN BENEATH THE M3-1 SIGN LOCATED 137' SOUTH OF POLE # 2/4-2/1			E-136B
SB	MM 0.031 LT	F	M6-1R	21	15		→	2.19					X													REPLACE EXISTING DIRECTIONAL ARROW SIGN BENEATH THE M1-5 SIGN LOCATED 137' SOUTH OF POLE # 2/4-2/1			E-136B
SB	MM 0.043 LT	F	M2-1	21	15		JCT						X		X											REMOVE EXISTING JUNCTION SIGN AND POST LOCATED 74' SOUTH OF POLE # 2/4-2/1			
SB	MM 0.043 LT	F	M1-5	30	24		VERMONT 108						X													REMOVE EXISTING STATE ROUTE SIGN BENEATH THE M2-1 SIGN LOCATED 74' SOUTH OF POLE # 2/4-2/1			
NB	MM 0.057 RT	A	W11-2	30	30	FYG		6.25								1		15								INSTALL A NEW PEDESTRIAN SIGN AND POST LOCATED ACROSS FROM POLE # 2/4-2/1	X		
NB	MM 0.057 RT	A	W16-7P	24	12	FYG		2.00																		INSTALL A NEW DOWNWARD DIAGONAL ARROW SIGN BENEATH THE NEW W11-2 LOCATED ACROSS FROM POLE # 2/4-2/1	X		
							NEW "STOP" SIGN ADDED @ MM 0.002+/- LT RI-1W/ NEW POST. SALVAGE EXISTING MM SIGN.																						
								SF 40.63	SF	EA 10	EA	EA	EA 10	EA	EA 5	EA 6	FT 90	FT 90	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: stowetrafficsign1.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
STOWE TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 56 OF 73