















# TRAFFIC SIGN SUMMARY SHEET

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL					
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	REMAIN		REMOVE	1.75	2.00	2.50	FOUNDATION	3.00	3.50			4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER	
																														lb/ft
NB	MM 1.279 RT	A	W11-4	30	30					X				X									RETAIN EXISTING CATTLE CROSSING SIGN AND POST LOCATED 533' SOUTH OF AND ACROSS FROM POLE # Z/A/4-2/35/34							
SB	MM 1.290 LT	F	R2-1	24	30			5.00						X		X		1	15					REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 475' SOUTH OF POLE # Z/A/4-2/35/34	X					
NB	MM 1.370 RT	D	R1-1	30	30			6.25						X		X		1	15					REPLACE EXISTING STOP SIGN AND POST LOCATED 53' SOUTH OF AND ACROSS FROM POLE # Z/A/4-2/35/34	X					
NB	MM 1.370 RT	A B	D3-1	48	12			4.00						X		X		2	30					REPLACE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 53' SOUTH OF AND ACROSS FROM POLE # Z/A/4-2/35/34		15				
SB	MM 1.389 LT	F	W11-4	30	30					X				X										RETAIN EXISTING CATTLE CROSSING SIGN AND POST LOCATED 48' NORTH OF POLE # Z/A/4-2/35/34						
NB	MM 1.410 RT	A	R2-1	24	30			5.00										1	15					INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 16' SOUTH OF POLE # IN/ED/35	X					
SB	MM 1.413 LT	F	W2-2L	30	30					X				X										RETAIN EXISTING SIDE ROAD LEFT SIGN AND POST LOCATED ACROSS FROM POLE # IN/ED/35						
SB	MM 1.413 LT	F	W16-8P	34	8					X														RETAIN EXISTING STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE EXISTING W2-2L SIGN LOCATED ACROSS FROM POLE # IN/ED/35						
NB	MM 1.441 RT	A	R2-1	24	30									X		X								REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED ADJACENT TO POLE # Vofs/48/36/48						
SB	MM 1.505 LT	F	R2-1	24	30			5.00						X		X		1	15					REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 37' NORTH OF AND ACROSS FROM POLE # 38/Vofs/50/42/50	X					
NB	MM 1.706 RT	A	W8-3	30	30			6.25										1	15					INSTALL A NEW PAVEMENT ENDS SIGN AND POST LOCATED 58' SOUTH OF THE INTERSECTION OF ALPINE VIEW ROAD	X					
NB	MM 1.709 RT	A	R2-1	24	30									X		X								REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 42' SOUTH OF THE INTERSECTION OF ALPINE VIEW ROAD						
NB	MM 1.720 RT	D	R1-1	30	30			6.25										1	15					INSTALL A NEW STOP SIGN AND POST LOCATED 16' NORTH OF THE INTERSECTION OF ALPINE VIEW ROAD	X					
NB	MM 1.720 RT	A B	D3-1	54	12			4.50										2	30					INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 16' NORTH OF THE INTERSECTION OF ALPINE VIEW ROAD		13				
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>										EA	EA	EA	EA	EA	EA	FT	FT	FT	LB	LB	LB	LB								
								SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
								42.25		10		9		10		150		150		EA		LB								

PROJECT NAME: STATEWIDE NORTHWEST REGION  
 PROJECT NUMBER: STP HRRR(17)  
 FILE NAME: stowetrafficsign4.dgn  
 PROJECT LEADER: J. DEVLIN  
 DESIGNED BY: N. PATTIS  
 STOWE TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 1/22/2014  
 DRAWN BY: N. PATTIS  
 CHECKED BY: B. GROSE  
 SHEET 59 OF 73