STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

STOWE
WEEKS HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.934 RT	A	W5-1	30	30		ROAD NARROWS	6.25								1		15								INSTALL A NEW ROAD NARROWS SIGN AND POST LOCATED 95' SOUTH OF AND ACROSS FROM POLE # V of F/66/52/66	X		
SB	MM 2.025 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 385' NORTH OF POLE # V of F/66/52/66	X		
NB	MM 2.205 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 639' SOUTH OF AND OPPOSITE THE INTERSECTION OF WELLS ROAD	X		
SB	MM 2.329 LT	F E	D3-1	30	12		Wells Rd	2.50					X		X	1		15								REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 16' NORTH OF THE INTERSECTION OF WELLS ROAD		15	
NB	MM 2.654 RT	A	W1-1L	30	30								X		X											REMOVE EXISTING TURN LEFT SIGN AND POST LOCATED 1336' NORTH OF AND ACROSS FROM POLE # 68			
NB	MM 2.654 RT	A	W13-1P	18	18		30 M.P.H.						X													REMOVE EXISTING SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L 1336' NORTH OF AND OPPOSITE POLE # 68			
NB	MM 2.690 RT	A	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 1526' NORTH OF AND OPPOSITE POLE # 68	X		
NB	MM 2.690 RT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L LOCATED 1526' NORTH OF AND OPPOSITE POLE # 68	X		
SB	MM 2.767 LT	F	W1-1R	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 1932' NORTH OF POLE # 68	X		
SB	MM 2.767 LT	F	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L LOCATED 1932' NORTH OF POLE # 68	X		
SB	MM 2.780 RT	F	W1-1R	30	30								X		X											REMOVE EXISTING TURN RIGHT SIGN AND POST LOCATED 1943' SOUTH OF MAILBOX # 256			
SB	MM 2.780 RT	F	W13-1P	18	18		30 M.P.H.						X													REMOVE EXISTING SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE W1-1R LOCATED 1943' SOUTH OF MAILBOX # 256			
SB	MM 3.005 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 755' SOUTH OF MAILBOX # 256	X		
NB	MM 3.189 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 216' NORTH OF AND ACROSS FROM MAILBOX # 256	X		
NB	MM 3.385 RT	A	W1-2L	30	30								X		X											REMOVE EXISTING CURVE LEFT SIGN AND POST LOCATED 264' SOUTH OF POLE # 65-S			
NB	MM 3.385 RT	A	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 264' SOUTH OF POLE # 65-S	X		
										EA	EA	EA	EA 10	EA	EA 8			FT 135				LB	LB	LB	LB					
								SF 52.00	SF	EA 10				EA 8		EA 9		FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: stowetrafficsign5.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
STOWE TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 60 OF 73