STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

STOWE
WEEKS HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 3.385 RT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L LOCATED 264' SOUTH OF POLE # 65-S	X		
NB	MM 3.435 RT	A	W1-8L	18	24								X		X											REMOVE EXISTING CHEVRON SIGN AND POST LOCATED ADJACENT TO POLE # 65-S			
NB	MM 3.436 RT	B	W1-6L	48	24			8.00								2		30								INSTALL A NEW LARGE LEFT ARROW SIGN ON TWO POSTS LOCATED 5' NORTH OF POLE # 65-S	X		
NB	MM 3.437 RT	A	W1-6R	48	24			8.00								2		30								INSTALL A NEW LARGE RIGHT ARROW SIGN ON TWO POSTS LOCATED 11' NORTH OF POLE # 65-S	X		
NB	MM 3.438 RT	A	W1-8L	18	24								X		X											REMOVE EXISTING CHEVRON SIGN AND POST LOCATED 16' NORTH OF POLE # 65-S			
SB	MM 3.473 LT	A	W1-2L	30	30								X		X											REMOVE EXISTING CURVE LEFT SIGN AND POST LOCATED 32' SOUTH OF POLE # 64/4-8-6/15/64			
SB	MM 3.473 LT	A	W1-1L	30	30			6.25								1		15								INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 32' SOUTH OF POLE # 64/4-8-6/15/64	X		
SB	MM 3.473 LT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L LOCATED 32' SOUTH OF POLE # 64/4-8-6/15/64	X		
NB	MM 3.583 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 549' NORTH OF AND ACROSS FROM POLE # 64/4-8-6/15/64	X		
SB	MM 3.893 LT	F E	D3-1	54	12		Edson Woods Rd	4.50								2		30								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED ADJACENT TO POLE # 53/5½/53		14	
NB	MM 4.005 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 591' NORTH OF AND ACROSS FROM POLE # 53/5½/53	X		
SB	MM 4.029 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		15								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 718' NORTH OF POLE # 53/5½/53	X		
SB	MM 4.138 LT	F	W11-7	30	30			6.25					X		X	1		15								REPLACE EXISTING EQUESTRIAN SIGN AND POST LOCATED 1294' NORTH OF POLE # 53/5½/53	X		
SB	MM 4.142 LT	H G	D3-1	48	12		Weeks Hill Rd	4.00								2		30								INSTALL A NEW STREET NAME SIGN AND POST LOCATED 1315' NORTH OF POLE # 53/5½/53		15	
								EA	EA	EA	EA	EA	EA				FT	FT	FT		LB	LB	LB	LB					
													7		7			195											
								SF 56.5	SF	EA 7				EA 7		EA 13	FT 195			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: stowetrafficsign6.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
STOWE TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 61 OF 73