STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

WESTFORD
ROLLIN IRISH ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.022 RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 432' WEST OF POLE # 90-1/4/143-1			
EB	MM 0.025 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																		INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 417' WEST OF POLE # 90-1/4/143-1		4	
WB	MM 0.101 LT	F	S3-4	30	30	FYG	SCHOOL BUS TURN AHEAD	6.25					X		X	1		15								REPLACE EXISTING SCHOOL BUS TURN AHEAD SIGN AND POST LOCATED 16' WEST OF AND ACROSS FROM POLE # 90-1/4/143-1	X		
EB	MM 0.103 RT	A	W5-1	30	30		ROAD NARROWS	6.25								1		15								INSTALL A NEW ROAD NARROWS SIGN AND POST LOCATED 5' WEST OF POLE # 90-1/4/143-1	X		
EB	MM 0.136 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																		INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 169' EAST OF POLE # 90-1/4/143-1		4	
EB	MM 0.320 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																		INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 1130' WEST OF AND ACROSS FROM MAILBOX # 239		4	
WB	MM 0.365 LT	F	W5-1	30	30		ROAD NARROWS	6.25								1		15								INSTALL A NEW ROAD NARROWS SIGN AND POST LOCATED 892' WEST OF MAILBOX 239	X		
EB	MM 0.482 RT TO MM 0.528 RT	A B		6	8		(8) TYPE II - 6" X 8" WHITE DELINEATORS	2.66																		INSTALL NEW DELINATORS (10) BACK-TO-BACK 60' APART ON 5 POSTS, INSTALL FIRST ONE 275' WEST OF AND ACROSS FROM MAILBOX # 239		4	
WB	MM 0.561 LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 143' EAST OF MAILBOX # 239			
WB	MM 0.645 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00								1		15								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 586' EAST OF MAILBOX # 239	X		
EB	MM 0.645 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		15								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 586' EAST OF AND ACROSS FROM MAILBOX # 239	X		
EB	MM 0.681 RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 771' WEST OF AND ACROSS FROM POLE # 17/21			
EB	MM 0.698 RT	A B		6	8		(2) TYPE II - 6" X 8" WHITE DELINEATORS	0.67																		INSTALL NEW DELINATORS (2) BACK-TO-BACK ON A POST LOCATED 681' WEST OF AND ACROSS FROM POLE # 17/21		4	
EB	MM 0.804 RT	A	W1-5R	30	30			6.25								1		15								INSTALL A NEW WINDING ROAD SIGN AND POST LOCATED 121' WEST OF AND ACROSS FROM POLE # 17/21	X		
EB	MM 0.983 RT TO MM 1.008 RT	A B		6	8		(4) TYPE II - 6" X 8" WHITE DELINEATORS	1.33																		INSTALL NEW DELINATORS (6) BACK-TO-BACK 60' APART ON 3 POSTS, INSTALL FIRST 90' WEST OF POLE # NET/17/17		4	
										EA	EA	EA	EA 4	EA	EA 4		FT	FT 90	FT		LB	LB	LB	LB				
								SF 41.65	SF	EA 4				EA 4		EA 6	FT 90			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(17)

FILE NAME: westfordtrafficsign1.dgn
PROJECT LEADER: J. DEVLIN
DESIGNED BY: N. PATTIS
WESTFORD TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 1/22/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 66 OF 73