













TRAFFIC SIGN SUMMARY SHEET

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL				
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	REPAIR		REPLACE	FOUNDA-TION	3.00	3.50	4.00	5.00	DETAIL IN SHSM			DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER			
																											1.75	2.00	2.50
WB	MM 1.094 LT	F	W1-5R	30	30			6.25								1	15						INSTALL A NEW WINDING ROAD SIGN AND POST LOCATED 74' WEST OF AND ACROSS FROM POLE # NET/14	X					
EB	MM 1.279 RT	A	R2-1	24	30			5.00									1	15					REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 903' EAST OF POLE # NET/14	X					
EB	MM 1.634 RT	A	W3-1	30	30			6.25									1	15					INSTALL A NEW STOP AHEAD SIGN AND POST LOCATED 253' WEST OF POLE # 17 1/2	X					
EB	MM 1.643 RT	A	W3-1	30	30																		REMOVE EXISTING STOP AHEAD SIGN AND POST LOCATED 206' WEST OF POLE # 17 1/2						
WB	MM 1.673 LT	F	R2-1	24	30																		REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 48' WEST OF AND ACROSS FROM POLE # 17 1/2						
WB	MM 1.673 LT	F	VR-501	24	30																		REMOVE EXISTING NO THRU TRUCKS SIGN LOCATED 48' WEST OF AND ACROSS FROM POLE # 17 1/2						
WB	MM 1.682 LT	F	VR-017	24	30																		REMOVE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # 17 1/2						
WB	MM 1.682 LT	F	R2-1	24	30			5.00									1	15					INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # 17 1/2	X					
EB	MM 1.688 RT	A	R1-1	30	30			6.25									1	15					REPLACE EXISTING STOP SIGN AND POST LOCATED 32' EAST OF POLE # 17 1/2	X					
WB	MM 1.688 LT	G H	D3-1	54	12			4.50									2	30					REPLACE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 32' EAST OF AND ACROSS FROM POLE # 17 1/2		15				
WB	MM 1.688 LT	F E	D3-1	48	12			4.00									2	30					INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 32' EAST OF AND ACROSS FROM POLE # 17 1/2		15				
EB	MM 1.696 CTR	J	W1-7	48	24			6.25									2	30					REPLACE EXISTING LARGE DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 95' EAST OF POLE # 17 1/2	X					
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>										EA	EA	EA	EA	EA	EA	8	7	FT	FT	FT	LB	LB	LB	LB					
								SF	SF	EA	EA	EA	EA	EA	11	FT	FT	FT	EA	LB									
								43.50		8	7	11	165	165															

PROJECT NAME: STATEWIDE NORTHWEST REGION
 PROJECT NUMBER: STP HRRR(17)
 FILE NAME: westfordtraffic2.dgn PLOT DATE: 1/22/2014
 PROJECT LEADER: J. DEVLIN DRAWN BY: N. PATTIS
 DESIGNED BY: N. PATTIS CHECKED BY: B. GROSE
 WESTFORD TRAFFIC SIGN SUMMARY SHEET 2 SHEET 67 OF 73