STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET

TOWN TOTALS

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (in) 1.75 lb/ft 1.88 | SQUARE STEEL (in) 2.00 lb/ft 2.42 | SQUARE STEEL (in) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(in) FOUNDATION | TUBULAR STEEL O/(in) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(in) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(in) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(in) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK | SIGN DETAIL DETAIL IN SHSM | SIGN DETAIL DETAIL ON SHEET NUMBER | SIGN DETAIL STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | BRISTOL TSSS SUBTOTAL | 199.66 | | | 2 | 2 | 33 | | 25 | 35 | | 525 | | | | | | | | | | | |
| | | | | | | | BRISTOL RIVER ROAD TSSS SUBTOTAL | 77.25 | | 2 | | | 6 | 2 | 7 | 12 | | 180 | | | | | | | | | | | |
| | | | | | | | GEORGIA TSSS SUBTOTAL | 294.82 | | 4 | | | 43 | 4 | 39 | 48 | | 720 | | | | | | | | | | | |
| | | | | | | | MILTON TSSS SUBTOTAL | 141.83 | | | | | 10 | | 10 | 23 | | 345 | | | | | | | | | | | |
| | | | | | | | MORETOWN TSSS SUBTOTAL | 557.58 | | | | | 36 | | 42 | 105 | | 1575 | | | | | | | | | | | |
| | | | | | | | RICHMOND TSSS SUBTOTAL | 278.65 | | 3 | | | 20 | 3 | 19 | 40 | | 600 | | | | | | | | | | | |
| | | | | | | | STOWE TSSS SUBTOTAL | 302.45 | | 6 | | | 46 | 5 | 37 | 59 | | 885 | | | | | | | | | | | |
| | | | | | | | SWANTON TSSS SUBTOTAL | 86.05 | | | | | 8 | | 8 | 17 | | 255 | | | | | | | | | | | |
| | | | | | | | WESTFORD TSSS SUBTOTAL | 85.15 | | | | | 12 | | 11 | 17 | | 255 | | | | | | | | | | | |
| | | | | | | | | SF 2023.44 | SF | EA 15 | EA 2 | EA 2 | EA 214 | EA 14 | EA 198 | EA 356 | FT | FT 5340 | FT | EA | LB | LB | LB | LB | | | | |
| | | | | | | | | | | EA 233 | | | | EA 212 | | | FT 5340 | | | EA | LB | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

**PROJECT NAME:** STATEWIDE NORTHWEST REGION
**PROJECT NUMBER:** STP HRRR(17)

**FILE NAME:** totaltrafficsignsumm.dgn
**PROJECT LEADER:** J. DEVLIN
**DESIGNED BY:** N. PATTIS
TRAFFIC SIGN SUMMARY TOTALS SHEET

**PLOT DATE:** 1/22/2014
**DRAWN BY:** N. PATTIS
**CHECKED BY:** B. GROSE
**SHEET** 69 **OF** 73