STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SUMMARY SHEET

BEGIN STATION	END STATION	POS.	900.645 SPECIAL PROVISION (VEHICLE SIGNAL HEADS, LED) 12" LED SIGNAL HEAD WITH BACKPLATES	12" LED SIGNAL HEAD WITH LEFT TURN ARROW AND BACK PLATES	SIGNAL HEAD MOUNTING EQUIPMENT	SIGNAL CABLE	900.620 PEDESTAL MOUNTED PEDESTRIAN SIGNAL HEAD, COUNTDOWN										REMARKS
			EACH	EACH	EACH	EACH	EACH										
ST ALBANS																	
US ROUTE 7 AT JC PENNY DRIVE																	
			7	1	5	5	2										HOUSING TO BE OF YELLOW POLY MATERIAL WITH BLACK VISORS
																	A NEW 3-SECTION SIGNAL HEAD IS TO BE ADDED ON THE POLE LOCATED ON THE NORTHEAST CORNER OF THE INTERSECTION FOR EASTBOUND TRAFFIC
TOTAL			7	1	5	5	2										

ITEM DETAIL SUMMARY SHEET		
	PROJECT NAME: STATEWIDE NORTHWEST REGION	
	PROJECT NUMBER: STP HRRR(17)	
	FILE NAME: itemdetailsheet3.dgn	PLOT DATE: 1/22/2014
	PROJECT LEADER: J. DEVLIN	DRAWN BY: N. PATTIS
	DESIGNED BY: N. PATTIS	CHECKED BY: B. GROSE
	ITEM DETAIL SUMMARY SHEET 3	SHEET 73 OF 73