STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

ROYALTON
ROYALTON HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.000 LT	H G	D3-1	66	12		Royalton Hill Rd			X				X												RETAIN EXISTING STREET NAME SIGN AND POST LOCATED AT THE ROYALTON BARNARD TOWN LINE			
SB	MM 1.203 LT	F E		6	8		(2) TYPE II 6"X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON 1 POST LOCATED 882' NORTH OF AND ACROSS FROM THE INTERSECTION OF UPPER LEA FARM ROAD AND ROYALTON HILL ROAD		4	
SB	MM 1.~~326~~ 320 LT	F E		6	8		(2) TYPE II 6"X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON 1 POST LOCATED ~~+420'~~ SOUTH OF AND ACROSS FROM MAILBOX # 2467	1387'	4	
SB	MM 1.406 LT	F E		6	8		(2) TYPE II 6"X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON 1 POST LOCATED 998' ~~NORTH~~ OF AND ACROSS FROM MAILBOX # 2467	SOUTH	4	
SB	MM 1.469 LT	E	W11-7	30	30								X													REMOVE EXISTING EQUESTRIAN SYMBOL SIGN FROM THE SIDE OF A TREE LOCATED 665' SOUTH OF AND ACROSS FROM MAILBOX # 2467			
NB	MM 1.596 RT	A	R2-1	24	30			5.00					X		X	1		~~15~~ 12.25								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED ~~5'~~ 13' NORTH OF MAILBOX # 2467	X		
NB	MM 1.684 RT	A	S3-1	30	30								X		X											REMOVE EXISTING SCHOOL BUS STOP AHEAD SIGN AND POST LOCATED 470' NORTH OF MAILBOX # 2467			
NB	MM 1.684 RT	A	S3-1	30	30	FYG		6.25								1		~~15~~ 11.25								INSTALL NEW SCHOOL BUS STOP SYMBOL SIGN AND POST LOCATED 470' NORTH OF MAILBOX # 2467	X		
SB	MM 1.810 LT - MM 2.003 LT	E F		6	8		36 ~~(34)~~ TYPE II 6"X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS 36~~(34)~~ BACK-TO-BACK 60 FEET APART ON 18~~17~~ POSTS. INSTALL THE FIRST ONE 1135' NORTH OF AND ACROSS FROM MAILBOX # 2467		4	
SB	MM 2.134 LT	F	R2-1	24	30			5.00					X		X	1		~~15~~ 12.25								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 528' SOUTH OF MAILBOX # 1861	X		
NB	MM 2.261 RT	A	R2-1	24	30			5.00					X		X	1		~~15~~ 12.75								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # CU6T/71/25/27	X		
SB	MM 2.611 LT	H	R1-1	30	30			6.25								1		~~15~~ 13								INSTALL NEW STOP SIGN AND POST LOCATED 586' NORTH OF POLE # NET/71/25/27	X		
NB	MM 2.613 RT	C	R1-1	30	30								X		X											REMOVE EXISTING STOP SIGN AND POST LOCATED 597' NORTH OF AND ACROSS FROM POLE #NET/71/ 25/ 27			
										EA 1	EA	EA	EA 6	EA 1	EA 5		FT	FT 75	FT		LB	LB	LB	LB					
								SF 27.50	SF	EA 7				EA 6		EA 5	FT ~~75~~ 61.5			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(18)

FILE NAME: 13K034wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
ROYALTON TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 1/3/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 19 OF 34