

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS					NO. OF NEW POSTS	SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL								
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN		REMOVE	FOUNDAION	lb/ft		lb/ft		DETAIL IN SHSM			DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER							
																		1.75	2.00	2.50	3.00						3.50	4.00	5.00				
NB	MM 2.613 RT	C	WI-7	48	24			8.00								2	12.25	30	12.25						INSTALL NEW DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 597' NORTH OF AND ACROSS FROM POLE # NET/71/25/27	X							
SB	MM 2.633 ⁶²⁸ LT	F	RI-1	24	30			5.00					X		X	1	15	14							REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 111' SOUTH OF AND ACROSS FROM POLE # 292/24	87	X						
NB	MM 2.638 RT	A	WI-2R	30	30										X	X									REMOVE EXISTING CURVE RIGHT SIGN AND POST LOCATED 84' SOUTH OF POLE # 292/24								
NB	MM 2.644 RT	A	WI-2R	30	30			6.25								1	15	13.5							INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 53' SOUTH OF POLE # 292/24	X							
SB	MM 2.662 LT	E F	WI-8R WI-8L	18 18	24 24			3.00 3.00								1	15	10.75							INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 42' NORTH OF AND ACROSS FROM POLE # 292/24	X							
SB	MM 2.682 LT	E F	WI-8R WI-8L	18 18	24 24			3.00 3.00								1	15	8							INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 26' SOUTH OF POLE # 23/21	X							
SB	MM 2.704 LT	E F	WI-8R WI-8L	18 18	24 24			3.00 3.00								1	15	9.75							INSTALL TWO NEW CHEVRONS ON ONE POST USING A BRACKET. LOCATE IT 90' NORTH OF POLE # 23/21	X							
SB	MM 2.734 LT	F	WI-1L	30	30			6.25								1	15	13							INSTALL NEW TURN LEFT SIGN AND POST LOCATED 95' SOUTH OF AND ACROSS FROM POLE # NET/71/20/22	X							
SB	MM 2.734 LT	F	W13-1P	18	18			2.25																	INSTALL NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS NEW WI-1L SIGN LOCATED 95' SOUTH OF AND ACROSS FROM POLE # NET/71/20/22	X							
NB	MM 2.969 RT	A	RI-1	24	30			5.00					X		X	1	15	13.25							REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 16' SOUTH OF POLE # 292	X							
SB	MM 3.004 LT	F	W11-7	30	30			6.25					X		X	1	15	13.25							REPLACE EXISTING EQUESTRIAN SIGN AND POST LOCATED 32' SOUTH OF POLE # NET/155	X							
							DAVIS ROAD																										
WB	MM 0.008 ¹² RT	A	R2-1	24	30			5.00								1	15	13.5							INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 116' SOUTH OF POLE # NET/32/32	95	X						
EB	MM 0.008 LT	F	RI-1	30	30			6.25								1	15	10.75							INSTALL NEW STOP SIGN AND POST LOCATED 116' SOUTH OF AND ACROSS FROM POLE # NET/32/32	X							
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".										EA	EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB								
							SF	SF		EA	EA	EA		FT	EA	LB																	
							68.25			4	4	12		180																			
														180																			
														144.25																			