STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

WILMINGTON
COLDBROOK ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.122 LT	F	W3-1	30	30			6.25					X		X	1		~~15~~ 13.75									REPLACE EXISTING STOP AHEAD SIGN AND POST LOCATED 132' NORTH OF POLE # NET/3/GMP/3	X		
NB	MM 0.516 RT	A	W1-2R	30	30								X		X												REMOVE EXISTING CURVE RIGHT SIGN AND POST LOCATED 106' SOUTH OF POLE # NET/14/GMP/1			
NB	MM 0.561 RT	A B	D3-1	30	12			2.50					X		X	1		~~15~~ 12									REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 132' NORTH OF POLE # NET/14/GMP/1		11	
NB	MM 0.571 RT	D	R1-1	30	30			6.25					X		X	1		~~15~~ 12.5									REPLACE EXISTING STOP SIGN AND POST LOCATED 16' SOUTH OF POLE # NET/15/GMP/1	X		
SB	MM 0.737 LT	H	R1-1	30	30			6.25					X		X	1		~~15~~ 12.75									REPLACE EXISTING STOP SIGN AND POST LOCATED 861' NORTH OF AND ACROSS FROM POLE # NET/15/GMP/1	X		
							BREAK IN PROJECT UNTIL MM 1.739																							
NB	MM 1.854 RT	A	W1-5L	30	30								X		X												REMOVE EXISTING WINDING ROAD SIGN AND POST LOCATED 16' NORTH OF POLE # NET/38/GMP/49			
NB	MM 1.854 RT	A	W16-8P	18	18								X														REMOVE EXISTING ADVISORY SPEED PLAQUE LOCATED BENEATH W1-5L SIGN LOCATED 16' NORTH OF POLE #NET/38/GMP/49			
NB	MM 1.892 RT	A	W1-5L	30	30			6.25								1		~~15~~ 16									INSTALL A NEW WINDING ROAD SIGN AND POST LOCATED 216' NORTH OF POLE # NET/38/GMP/49	X		
NB	MM 1.892 RT	A	W16-8P	18	18			2.25																			INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE EXISTING W1-5L SIGN LOCATED 216' NORTH OF POLE # NET/38/GMP/49	X		
SB	MM 1.915 LT	F	R2-1	24	30			5.00					X		X	1		~~15~~ 13.25									REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 338' NORTH OF AND ACROSS FROM POLE # NET/38/GMP/49	X		
SB	MM 1.930 LT - MM 2.010 LT	E F		6	8		(14) TYPE II 6"X 8" WHITE DELINEATORS																				INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60 FEET APART ON 7 POSTS, INSTALL FIRST 417' NORTH OF AND ACROSS FROM POLE # NET/38/GMP/49		4	
SB	MM 2.186 LT	F	W1-5L	30	30								X		X												REMOVE EXISTING WINDING ROAD SIGN AND POST LOCATED 628' SOUTH OF POLE # 47/GMP/60			
SB	MM 2.186 LT	F	W16-8P	18	18								X														REMOVE EXISTING ADVISORY SPEED PLAQUE LOCATED BENEATH W1-5L SIGN LOCATED 628' SOUTH OF POLE # 47/GMP/60			
										EA	EA	EA	EA 10	EA	EA 8		FT	FT 90	FT		LB	LB	LB	LB					
								SF 34.75	SF	EA 10				EA 8		EA 6	FT ~~90~~ 80.25			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(18)

FILE NAME: 13K034wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
COLDBROOK RD. TRAFFIC SIGN SUMM. SHEET 2

PLOT DATE: 1/3/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE