STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

WILMINGTON
HIGLEY HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.051 RT	A	W11-6H	30	30			6.25					X		X	1		~~15~~ 13'								REPLACE SNOWMOBILE SIGN WITH A NEW HINGED SNOWMOBILE SIGN AND POST LOCATED 158' WEST OF POLE # NET/30/GMP/12/3		10	
WB	MM 1.068 LT	F	W1-4R	30	30			6.25								1		15								INSTALL A NEW REVERSE CURVE RIGHT SIGN ON A NEW POST LOCATED 69' WEST OF AND ACROSS FROM POLE # NET/30/GMP/12/3	X		
EB	MM 1.145 RT	A	R2-1	24	30			5.00					X		X	1		~~15~~ 13.25								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 26' WEST OF POLE # GMP/32/32	X		
WB	MM 1.145 LT	F	R2-1	24	30			5.00								1		~~15~~ 15.5								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 26' WEST OF AND ACROSS FROM POLE # GMP/32/32	X		
WB	MM 1.215 LT	F	R2-1	24	30								X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 343' EAST OF AND ACROSS FROM POLE # GMP/32/32			
EB WB	MM 1.215 LT/RT						POSTS						3		~~X~~											REMOVE EXISTING POSTS ON BOTH SIDES OF THE ROAD LOCATED 343' EAST OF POLE # GMP/32/32			
EB	MM 1.437 RT	A	W1-2L	30	30			6.25								1		15								INSTALL A NEW CURVE LEFT SIGN AND POST LOCATED 42' WEST OF POLE # NET/4/GMP/41/19286	X		
EB	MM 1.445 RT - MM 1.538 RT	A B		6	8		(14) TYPE II - 6"X 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (14) BACK-TO-BACK 70 FEET APART ON 7 POSTS. INSTALL FIRST ADJACENT TO POLE # NET/4/GMP/41/19286		4	
WB	MM 1.588 LT	F	W1-060	30	30			6.25					X		X	1		~~15~~ 16.75								REPLACE EXISTING HIDDEN DRIVES SIGN AND POST LOCATED 32' WEST OF POLE # NET/12/45/45/19303		10	
WB	MM 1.588 LT	F	W1-2R	30	30			6.25																		INSTALL A NEW CURVE RIGHT SIGN ABOVE AND ON THE SAME POST AS NEW VW-60 SIGN LOCATED 32' WEST OF POLE # NET/12/45/45/19303	X		
WB	MM 1.718 LT	F	R2-1	24	30			~~6.25~~ 5.00					X		X	1		~~15~~ 12.5								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 74' EAST OF POLE # NET/49/GMP/49	X		
WB	MM 1.760 LT	H	R1-1	30	30			6.25					X		X	1		~~15~~ 12.5								REPLACE EXISTING STOP SIGN AND POST LOCATED 11' WEST OF AND ACROSS FROM POLE # 1931/127/NET/12/50/GMP/50	X		
EB	MM 1.771 RT	A	W1-10L	36	36			9.00					X		X	2		15.75 30 16.25								REPLACE EXISTING CURVE LEFT, SIDEROAD SIGN ON TWO NEW POSTS LOCATED 48' EAST OF POLE # 1937/127/NET/12/ 50/ GMP/50	X		
								SF ~~62.75~~ 61.5	SF	EA 7			EA ~~7~~ 10	EA 8		EA 10		FT ~~150~~ 145.5		EA	LB							
										EA	EA	EA		EA	EA		FT	FT	FT		LB	LB	LB	LB				
															8			150											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(18)

FILE NAME: 13K034wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 1/3/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
HIGLEY HILL RD. TRAFFIC SIGN SUMM. SHEET 2 SHEET 28 OF 34