STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

WILMINGTON
HIGLEY HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.771 RT	A	W16-8P	43	8		Lake Raponda Rd	2.38																		INSTALL NEW ADVANCED STREET NAME SIGN LOCATED BENEATH AND ON THE SAME POST AS THE NEW W1-10L SIGN LOCATED 48' EAST OF POLE # 1931/127/NET/12/50/GMP/50		11	
WB	MM 1.773 LT	F	D3-1	42	12		Haynes Rd	3.50					X		X	1		15 10.25								REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 58' EAST OF AND ACROSS FROM POLE # 1931/127/NET/12/50/GMP/50		11	
WB	MM 1.773 LT	G	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1		15 13.25								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 58' EAST OF AND ACROSS FROM POLE # 1931/127/NET/12/50/GMP/50	X		
WB	MM 1.836 LT	F	W2-2	30	30			6.25								1		~~15~~ 14.75								INSTALL A NEW INTERSECTION RIGHT SIGN AND POST LOCATED ACROSS FROM POLE # 515/19321	X		
WB	MM 1.836 LT	F	W16-8P	28	8		Haynes Rd	1.55																		INSTALL A NEW ADVANCED STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2 SIGN LOCATED ACROSS FROM POLE # 515/19321		11	
EB	MM 1.840 RT	A B	D3-1	66	12		Lake Raponda Rd	5.50					X		X	2		10.25 30 11'								REPLACE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 21' EAST OF POLE # 515/19321		11	
EB	MM 1.848 RT	D	R1-1	30	30		STOP	6.25					X		X	1		~~15~~ 13.5								REPLACE EXISTING STOP SIGN AND POST LOCATED 63' EAST OF POLE # 515/19321	X		
WB	MM 1.910 LT	F	W1-10	36	36			9.00								2		15.75 30 15'								INSTALL A NEW CURVE RIGHT, INTERSECTION SIGN ON TWO POSTS LOCATED 69' WEST OF POLE # 53	X		
WB	MM 1.910 LT	F	W16-8P	43	8		Lake Raponda Rd	2.38																		INSTALL NEW ADVANCED STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-10R LOCATED 69' WEST OF POLE # 53		11	
										EA	EA	EA	EA 4	EA	EA 4		FT	FT 120	FT		LB	LB	LB	LB					
								SF 41.81	SF	EA 4				EA 4		EA 8	FT ~~120~~ 103.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(18)

FILE NAME: 13K034wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
HIGLEY HILL RD. TRAFFIC SIGN SUMM. SHEET 3

PLOT DATE: 1/3/2014
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE