

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	BRIDGE	EROSION CONTROL	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1300			1300		CY	EARTH BORROW	203.30	EST.			
							1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	--			
							16			16		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							16			16		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							16			16		HR	TRUCK RENTAL	608.37	EST.			
							16			16		HR	LOADER RENTAL, TYPE I	608.40	EST.			
							5530			5530		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	56			
							38			38		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	--			
							5235			5235		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	56			
							24			24		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							275			275		HR	FLAGGERS	630.15	EST.			
							1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	--			
							1			1		LS	TRAFFIC CONTROL	641.10				
							4885			4885		LF	4 INCH YELLOW LINE	646.21	49			
							240			240		LF	24 INCH STOP BAR	646.26	--			
							116			116		EACH	LETTER OR SYMBOL	646.30	--			
									23	23		LB	SEED	651.15	EST.			
									93	93		LB	FERTILIZER	651.18	EST.			
									0.045	0.045		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
									0.371	0.371		TON	HAY MULCH	651.25	EST.			
							100			100		CY	TOPSOIL	651.35	1			
									900	900		SY	TEMPORARY EROSION MATTING	653.20	EST.			
							2400			2400		SF	TRAFFIC SIGNS, TYPE A	675.20	27.33			
							6470			6470		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	65			
							319			319		EACH	REMOVING SIGNS	675.50	--			
							60			60		EACH	DELINEATOR WITH STEEL POST	676.10	1			
							1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	--			

ITEM DETAIL SUMMARY SHEET	PROJECT NAME: STATEWIDE SOUTHWEST REGION
	PROJECT NUMBER: STP HRRR(19)
	FILE NAME: I3k036wrk.dgn
	PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS	PLOT DATE: 1/7/2014
QUANTITY SHEET	DRAWN BY: N. PATTIS
	CHECKED BY: B. GROSE
	SHEET 3 OF 87