STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

BENNINGTON
OVERLEA ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							OVERLEA ROAD																						
WB	MM 0.007 LT	G	VD-024	72	10		N. Bennington / Bennington	5.00					2			2		24.0 ~~30~~								INSTALL A NEW TOWN LINE SIGN ON TWO NEW POSTS LOCATED 21' WEST OF AND ACROSS FROM POLE # 80/46		16	
EB	MM 0.041 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		13.25 ~~15~~								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 158' EAST OF POLE # 80/46	X		
WB	MM 0.082 LT	F	W10-1	36	36		R R	7.07								1		14.25 ~~15~~								INSTALL A NEW RAILROAD CROSSING SIGN AND POST LOCATED 48' WEST OF AND ACROSS FROM POLE # NET/49/46	X		
WB	MM 0.123 LT	F	W10-1	30	30		R R						X		X											REMOVE EXISTING RAILROAD CROSSING SIGN AND POST LOCATED 169' EAST OF AND ACROSS FROM POLE # NET/49/46			
EB	MM 0.654 RT	A	W3-1	30	30			6.25					X		X	1		15.75 ~~15~~								REPLACE EXISTING STOP AHEAD SIGN AND POST LOCATED 11' WEST OF POLE # 76/3/3	X		
WB	MM 0.690 LT	F	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE THE EXISTING SPEED LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # 76/2/2			
WB	MM 0.725 LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X											REMOVE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED 185' EAST OF AND ACROSS FROM POLE # 76/2/2			
WB	MM 0.733 LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		15.75 ~~15~~								INSTALL A NEW LEGAL LOAD LIMIT SIGN AND POST LOCATED 227' EAST OF AND ACROSS FROM POLE # 76/2/2		18	
WB	MM 0.733 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00																		INSTALL A NEW SPEED LIMIT SIGN BENEATH AND ON THE SAME POST AS THE NEW VR-17 SIGN LOCATED 227' EAST OF AND ACROSS FROM POLE # 76/2/2	X		
EB	MM 0.740 RT	C D	D3-1	42	12		Overlea Rd	3.50					X		X	1		14.25 ~~15~~								REPLACE THE EXISTING STREET NAME SIGN AND POST LOCATED 264' EAST OF POLE # 76/2/2		15	
EB	MM 0.740 RT	A	R1-1	30	30		STOP	6.25					2 ~~1~~													REPLACE THE EXISTING STOP SIGN BENEATH AND ON THE SAME POST AS THE NEW D3-1 SIGN LOCATED 264' EAST OF POLE # 76/2/2	X		
								SF 43.07	SF	EA 7 ~~10~~	EA	EA	EA 10 ~~7~~	EA 6	EA 6	EA 7	FT 105 ~~97.25~~	FT 97.25 ~~105~~	FT	EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE