STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

DORSET
MAD TOM ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.216 LT	E F	D3-1	36	12		Leary Ln	3.00					X		X	1		13.75 ~~15~~									REPLACE THE EXISTING STREET NAME SIGN AND POST LOCATED 26' SOUTH OF POLE # NET/11/11		14	
SB	MM 0.216 LT	H	R1-1	30	30		STOP	6.25					X														REPLACE EXISTING STOP SIGN BENEATH AND ON THE SAME POST AS THE NEW D3-1 SIGN LOCATED 26' SOUTH OF POLE # NET/11/11	X		
NB	MM 0.226 RT	A	W1-1L	30	30			6.25								1		14.0 ~~15~~									INSTALL A NEW TURN LEFT SIGN AND POST LOCATED ACROSS FROM POLE # NET/11/11	X		
NB	MM 0.317 RT	A	W1-6L	48	24			8.00								2		23.0 ~~30~~									INSTALL A NEW LARGE LEFT ARROW ON TWO NEW POSTS LOCATED 106' SOUTH OF AND ACROSS FROM POLE # 13/NET/16	X		
NB	MM 0.318 RT	B	W1-6R	48	24			8.00								2		21.5 ~~30~~									INSTALL A NEW LARGE RIGHT ARROW SIGN ON TWO NEW POSTS LOCATED 100' SOUTH OF AND ACROSS FROM POLE # 13/NET/16	X		
SB	MM 0.334 LT	F	R2-1	24	30		SPEED LIMIT 35						X		X												REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 16' SOUTH OF POLE # 13/NET/16			
SB	MM 0.337 LT	F	W1-1R	30	30			6.25								1		14.0 ~~15~~									INSTALL A NEW TURN RIGHT SIGN AND POST LOCATED ADJACENT TO POLE # 13/NET/16	X		
NB	MM 0.404 RT	A	R2-1	24	30		SPEED LIMIT 25	5.00					X		X	1		10.75 ~~15~~									REPLACE THE EXISTING SPEED LIMIT SIGN AND POST LOCATED 5' NORTH OF POLE # 15/22/18/NET	X		
SB	MM 0.421 LT	F	R2-1	24	30		SPEED LIMIT 25	5.00								1		11.75 ~~15~~									INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 95' NORTH OF AND ACROSS FROM POLE # 15/22/18/NET	X		
SB	MM 0.484 LT	F	TOWN SIGN	30	30		WATCH FOR CHILDREN						X		X												REMOVE EXISTING WATCH FOR CHILDREN SIGN AND POST LOCATED 428' NORTH OF AND ACROSS FROM POLE # 15/22/18/NET			
NB	MM 0.575 RT	A	W1-1L	30	30			6.25								1		14.0 ~~15~~									INSTALL A NEW TURN LEFT SIGN AND POST LOCATED ACROSS FROM POLE # NET/22/23/23	X		
NB	MM 0.608 RT	A	W1-6L	48	24			8.00								2		25.75 ~~30~~									INSTALL A NEW LARGE LEFT ARROW ON TWO NEW POSTS LOCATED 95' SOUTH OF POLE # NET/22/25/25	X		
NB	MM 0.609 RT	B	W1-6R	48	24			8.00								2		25.75 ~~30~~									INSTALL A NEW LARGE RIGHT ARROW ON TWO NEW POSTS LOCATED 90' SOUTH OF POLE # NET/22/25/25	X		
								SF 70.00	SF	EA 5				EA 4		EA 14		FT ~~210~~ 174.25		EA									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
DORSET TRAFFIC SIGN SUMMARY SHEET 2
SHEET 22 **OF** 87