STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

DORSET
MAD TOM ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.993 LT	F	W1-1L	30	30			6.25								1		13.0 ~~15~~									INSTALL A NEW TURN LEFT SIGN AND POST LOCATED 63' SOUTH OF AND ACROSS FROM POLE # 6/213-3/NET	X		
NB	MM 3.007 RT	A	W2-2L	30	30			6.25								1		13.0 ~~15~~									INSTALL A NEW INTERSECTION LEFT SIGN AND POST LOCATED 116' SOUTH OF AND ACROSS FROM POLE # NET/73/213-1	X		
NB	MM 3.007 RT	A	W16-8P	36	8			2.00																			INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2L SIGN LOCATED 116' SOUTH OF AND ACROSS FROM POLE # NET/73/213-1		16	
SB	MM 3.102 LT	F	R2-1	24	30			5.00					~~X~~		X	1		11.25 ~~15~~									REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 16' NORTH OF POLE # NET/73/213-1	X		
SB	MM 3.118 LT	E F	D3-1	48	12			4.00								2		17.25 ~~30~~									INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 100' NORTH OF POLE # NET/73/213-1		13	
SB	MM 3.118 LT	H	R1-1	30	30			6.25								1		12.25 ~~15~~									INSTALL A NEW STOP SIGN AND POST LOCATED 100' NORTH OF POLE # NET/73/213-1	X		
NB	MM 3.121 RT	A B	D3-1	48	12								X														REMOVE EXISTING STREET NAME SIGN LOCATED 111' SOUTH OF AND ACROSS FROM POLE # NET/>22-2/74/214			
NB	MM 3.121 RT	C	R1-1	30	30								X		X												REMOVE EXISTING STOP SIGN AND POST LOCATED 111' SOUTH OF AND ACROSS FROM POLE # NET/>22-2/74/214			
NB	MM 3.122 RT	C	W1-7	48	24			8.00								2		24.0 ~~30~~									INSTALL A NEW LARGE DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 106' SOUTH OF AND ACROSS FROM POLE # NET/>22-2/74/214	X		
NB	MM 3.142 RT	A	R2-1	24	30			5.00								1		12.25 ~~15~~									INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED ACROSS FROM POLE # NET/>22-2/74/214	X		
NB	MM 3.199 RT	A	R2-1	24	30								X		X												REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 48' NORTH OF POLE # 215/NET/22/75			
NB	MM 4.000 RT	A	VR-023B	24	30			5.00								1		12.25 ~~15~~									INSTALL A NEW $500 FINE FOR LITTERING SIGN ACROSS FROM THE EXISTING NEW ENGLAND FORESTRY FOUNDATION SIGN		18	
SB	MM 4.314 LT	F	VR-017	24	30								X		X												REMOVE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED 116' SOUTH OF THE DORSET MOUNT TABOR TOWN LINE			
								SF 47.75	SF	EA ~~5~~ 4				EA 4		EA 10		FT ~~150~~ 115.25		EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE

DORSET TRAFFIC SIGN SUMMARY SHEET 5 **SHEET** 25 **OF** 87