STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

LEICESTER
LEICESTER-WHITING ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS ''A''	NEW SIGNS ''B''	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.102 RT	A	S3-2	30	30	FYG		6.25					X			1		14.5 ~~15~~								INSTALL A NEW SCHOOL BUS TURN AHEAD SIGN AND POST LOCATED 69' EAST OF POLE # 5	X		
EB	MM 0.144 RT	A	R2-1	24	30			5.00					X		X	1		13.25 ~~15~~								REPLACE THE EXISTING SPEED LIMIT SIGN AND POST LOCATED 90' EAST OF POLE # 84	X		
WB	MM 0.144 LT	F	R2-1	24	30			5.00								1		14.25 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 90' EAST OF AND ACROSS FROM POLE # 84	X		
EB	MM 0.154 RT	A	TOWN SIGN	30	30								X		X											REMOVE THE EXISTING PEDESTRIAN CROSSING SYMBOL LOCATED 69' WEST OF POLE # 8/3			
EB	MM 0.268 RT	C	TOWN SIGN	24	30								X		X											REMOVE EXISTING CHILDREN AT PLAY SIGN AND POST LOCATED ADJACENT TO POLE # 49/79/1			
EB	MM 0.268 RT	A B	D3-1	54	12			4.50					X			2		21.25 ~~30~~								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED ADJACENT TO POLE # 49/79/1		13	
EB	MM 0.334 RT	A	W11-2	30	30	FYG		6.25								1		15								INSTALL A NEW PEDESTRIAN CROSSING SIGN AND POST LOCATED 53' WEST OF POLE # 128/49	X		
EB	MM 0.334 RT	A	W16-7P	24	12	FYG		2.00																		INSTALL A NEW DIAGONAL ARROW PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W11-2 SIGN LOCATED 53' WEST OF POLE # 128/49	X		
WB	MM 0.374 LT	F	W11-2	30	30	FYG		6.25								1		15.25 ~~15~~								INSTALL A NEW PEDESTRIAN CROSSING SIGN AND POST LOCATED 32' WEST OF AND ACROSS FROM POLE # 223	X		
EB	MM 0.374 LT	F	W16-7P	24	12	FYG		2.00																		INSTALL A NEW ARROW PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W11-2 SIGN LOCATED 32' EAST OF POLE # 128/ 49	X		
EB	MM 0.399 RT	A	TOWN SIGN	24	30								X		X											REMOVE EXISTING CHILDREN AT PLAY SIGN AND POST LOCATED 100' EAST OF POLE # 223			
EB	MM 0.420 RT	A	W1-1	30	30								X		X											REMOVE EXISTING TURN RIGHT SIGN AND POST LOCATED 11' EAST OF POLE # 49/74-1			
										EA	EA	EA	EA ~~5~~ 7	EA	EA 5		FT	FT ~~105~~ 93.50	FT		LB	LB	LB	LB					
								SF 37.25	SF	EA ~~5~~ 7				EA 5		EA 7	FT ~~105~~ 93.50			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
LEICESTER TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 28 **OF** 87