STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

LEICESTER
LEICESTER-WHITING ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS ''A''	NEW SIGNS ''B''	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.430 LT	F	TOWN SIGNS	30	30								X		X											REMOVE EXISTING CHURCH CROSSING SIGN AND POST LOCATED 63' EAST OF AND ACROSS FROM POLE # 49/74-1			
EB	MM 0.438 RT	A	W1-1R	30	30			6.25								1		15.5 ~~15~~								INSTALL A NEW TURN RIGHT SIGN AND POST LOCATED 290' WEST OF AND ACROSS FROM POLE # 72/220	X		
EB	MM 0.438 RT	A	W13-1P	18	18			2.25																		INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE EXISTING W1-1R SIGN LOCATED 290' WEST OF AND ACROSS FROM POLE # 72/ 220	X		
WB	MM 0.460 LT	F	W1-8L	18	24								X		X											REMOVE EXISTING LEFT CHEVRON AND POST LOCATED 174' WEST OF POLE # 72/ 220			
WB	MM 0.464 LT	F	W1-6L	48	24			8.00								2		28.25 ~~30~~								INSTALL A NEW LARGE ARROW SIGN ON TWO NEW POSTS LOCATED 153' WEST OF POLE # 72/220	X		
WB	MM 0.472 LT	E	W1-6R	48	24			8.00								2		26.0 ~~30~~								INSTALL A NEW RIGHT ARROW SIGN ON TWO NEW POSTS LOCATED 111' WEST OF POLE # 72/220	X		
WB	MM 0.473 LT	F	W1-6L	48	24								X		X											REMOVE EXISTING LARGE ARROW LEFT SIGN AND POSTS LOCATED 106' WEST OF POLE # 72/220			
WB	MM 0.473 LT	F	OM1-1	18	18								X													REMOVE EXISTING 9 BALL SIGN LOCATED 106' WEST OF POLE # 72/ 220			
EB	MM 0.482 RT	A	W10-1	36	36					X				X												RETAIN EXISTING RAILROAD CROSSING SIGN AND POST LOCATED 58' WEST OF AND ACROSS FROM POLE # 72/220			
WB	MM 0.512 LT	F	W1-1L	30	30			6.25					X		X	1		15								REPLACE EXISTING TURN LEFT SIGN AND POST LOCATED 5' EAST OF POLE # NET/219	X		
WB	MM 0.512 LT	F	W13-1P	18	18			2.25																		INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-1L SIGN LOCATED 5' EAST OF POLE NET/219	X		
WB	MM 0.587 LT	F	R2-1	24	30								X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 169' EAST OF AND ACROSS FROM POLE # 121			
										EA 1	EA	EA	EA 6	EA 1	EA 5		FT	FT ~~90~~ 84.75	FT		LB	LB	LB	LB					
								SF 33.00	SF	EA 7				EA 6		EA 6	FT ~~90~~ 84.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE