STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

LEICESTER
LEICESTER-WHITING ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS ''A''	NEW SIGNS ''B''	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.616 RT	A	R1-3P	18	6		ALL WAY	0.75					X													INSTALL A NEW ALL WAY SIGN BENEATH AND ON THE SAME POST AS THE NEW R1-1 SIGN LOCATED 85' EAST OF AND ACROSS FROM POLE # NET/1/184/2232/1/25T	X		
WB	MM 1.616 LT	E	R1-1	30	30		STOP	6.25								1		13.75 ~~15~~								INSTALL A NEW STOP SIGN AND POST LOCATED 85' EAST OF POLE # NET/1/184/2232/1/25T	X		
WB	MM 1.616 LT	E	R1-3P	18	6		ALL WAY	0.75																		INSTALL A NEW ALL WAY SIGN BENEATH AND ON THE SAME POST AS THE NEW R1-1 SIGN LOCATED 85' EAST OF POLE # NET/1/184/2232/1/25T	X		
WB	MM 1.616 LT	H	R1-1	30	30		STOP	6.25					X		X	1		13.75 ~~15~~								REPLACE EXISTING STOP SIGN AND POST LOCATED 85' EAST OF POLE # NET/1/184/2232/1/25T	X		
WB	MM 1.616 LT	H	R1-3P	18	6		ALL WAY	0.75					X													INSTALL A NEW ALL WAY SIGN BENEATH AND ON THE SAME POST AS THE NEW R1-1 SIGN (H DIRECTION) LOCATED 85' EAST OF POLE # NET/1/184/2232/1/25T	X		
EB	MM 1.660 RT	A	R2-1	24	30		SPEED LIMIT 45	5.00					X		X	1		13.25 ~~15~~								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 53' WEST OF AND ACROSS FROM POLE # 223/41	X		
WB	MM 1.672 LT	F	D1-1	72	12		↑ Brandon 5	6.00								2		25.0 ~~30~~								INSTALL A NEW D-BOARD SIGN ON TWO NEW POSTS LOCATED 11' EAST OF POLE # 223/40/NET/12		17	
WB	MM 1.672 LT	F	D1-1	72	12		Whiting 4 →	6.00																		INSTALL A NEW D-BOARD SIGN BENEATH AND ON THE SAME POSTS AS THE NEW D1-1 SIGN LOCATED 11' EAST OF POLE # 223/40/NET/12		18	
WB	MM 1.732 LT	F	W3-1	30	30			6.25					X		X	1		14.0 ~~15~~								REPLACE EXISTING STOP AHEAD SIGN AND POST LOCATED 116' WEST OF POLE # 3	X		
EB	MM 1.827 RT	A	W1-1R	30	30								2 ~~X~~		X											REMOVE EXISTING TURN RIGHT SIGN AND POST LOCATED 21' EAST OF AND ACROSS FROM POLE # 223/37/NET/1-/5			
EB	MM 1.843 RT	A	W1-1R	30	30			6.25								1		15.25 ~~15~~								INSTALL A NEW TURN RIGHT SIGN AND POST LOCATED 90' WEST OF AND ACROSS FROM POLE # 6/36	X		
EB	MM 1.843 RT	A	W13-1P	18	18		20 M.P.H.	2.25																		INSTALL A NEW 20 MPH PLAQUE BENEATH AND ON THE SAME POST AS THE NEW TURN RIGHT SIGN LOCATED 90' WEST OF AND ACROSS FROM POLE # 6/36	X		
EB	MM 1.881 LT	F	R2-1	24	30		SPEED LIMIT 45	5.00					X		X	1		12.75 ~~15~~								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 90' WEST OF POLE # 35/7	X		
										EA	EA	EA	EA ~~5~~ ~~8~~	EA	EA 5		FT	FT ~~120~~ 107.75	FT		LB	LB	LB	LB					
								SF 51.50	SF	EA ~~5~~ ~~8~~				EA 5		EA 8	FT ~~120~~ 107.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE