STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

LEICESTER
LEICESTER-WHITING ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 3.161 LT	F	S4-3P	24	8	FYG	SCHOOL	1.33																		INSTALL A NEW SCHOOL PLAQUE BENEATH AND ON THE SAME POST AS THE NEW S1-1 SIGN LOCATED 100' EAST OF POLE # 2/2	X		
WB	MM 3.172 LT	F	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		15								INSTALL A NEW LEGAL LOAD LIMIT SIGN AND POST LOCATED 158' EAST OF POLE # 2/2		18	
WB	MM 3.172 LT	F	R2-1	24	30		SPEED LIMIT 30	5.00					X		X											REPLACE THE EXISTING SPEED LIMIT SIGN BENEATH AND ON THE SAME POST AS THE NEW VR-017 SIGN LOCATED 158' EAST OF POLE # 2/2	X		
EB	MM 3.182 RT	A	R1-1	30	30		STOP	6.25					X		X	1		~~15~~ 12.75								REPLACE THE EXISTING STOP SIGN AND POST LOCATED 211' EAST OF AND ACROSS FROM POLE # 2/2	X		
WB	MM 3.182 LT	E	R1-1	30	30		STOP	6.25					X		X	1		~~15~~ 13.25								REPLACE THE EXISTING STOP SIGN AND POST LOCATED 211' EAST OF POLE # 2/2	X		
EB	MM 3.182 RT	C D	D3-1	72	12		Leicester Whiting Rd	6.00					X			2		~~30~~ 22.5								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 211' EAST OF AND ACROSS FROM POLE # 2/2		14	
							JENNA LANE																					
SB	MM 0.006 LT	H G	D3-1	36	12		Jenna Ln	3.00					X		X	1		~~15~~ 14.0								REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 32' NORTH OF THE INTERSECTION OF LEICESTER WHITING ROAD AND JENNA LANE		14	
SB	MM 0.006 LT	F	R1-1	30	30		STOP	6.25					X													REPLACE EXISTING STOP SIGN BENEATH AND ON THE SAME POST AS THE NEW D3-1 SIGN LOCATED 32' NORTH OF THE INTERSECTION OF JENNA LANE AND LEICESTER WHITING ROAD	X		
SB	MM 0.006 LT	H G	D3-1	72	12		Leicester Whiting Rd						X													REMOVE EXISTING STREET NAME SIGN LOCATED 32' NORTH OF THE INTERSECTION OF JENNA LANE AND LEICESTER WHITING ROAD			
NB	MM 0.020 RT	A	W14-2	30	30		NO OUTLET	6.25								1		~~15~~ 14.0								INSTALL A NEW NO OUTLET SIGN AND POST LOCATED 121' SOUTH OF POLE # 2/NET	X		
SB	MM 0.020 LT	F	W14-1	30	30		DEAD END						X		X											REMOVE EXISTING DEAD END SIGN AND POST LOCATED 121' WEST OF AND ACROSS FROM POLE # 2/NET			
SB	MM 0.020 LT	F	R2-1	24	30		SPEED LIMIT 10						X													REMOVE THE EXISTING SPEED LIMIT SIGN LOCATED 121' WEST OF AND ACROSS FROM POLE # 2/NET			
							OLD JERUSALEM ROAD																					
WB	MM 0.007 LT	F	R1-1	30	30		STOP	6.25					X		X	1		~~15~~ 13.0								REPLACE EXISTING STOP SIGN AND POST LOCATED 180' WEST OF POLE # 1-12/1	X		
										EA	EA	EA	EA ~~9~~ 10	EA	EA 6		FT	FT ~~120~~ 104.50	FT			LB	LB	LB	LB					
								SF 51.58	SF	EA ~~9~~ 10				EA 6		EA 8	FT	FT ~~120~~ 104.50		EA	LB									

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE