STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

LEICESTER
SWINGINGTON HILL ROAD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 0.007 LT	G H	D3-1	66	12		Old Jerusalem Rd	5.50					X		X	2		25.0 ~~30~~								REPLACE THE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 180' WEST OF POLE # 1-12/1		15	
EB	MM 0.024 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		13.75 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 90' WEST OF AND ACROSS FROM POLE # 1-12/1	X		
EB	MM 0.057 RT	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 84' EAST OF AND ACROSS FROM POLE # 1-12/1			
							SWININGTON HILL ROAD																						
NB	MM 0.000 LT	G H	D3-1	72	12		Leicester Whiting Rd	6.00								2		25.25 ~~30~~								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 169' NORTH OF POLE # 181		14	
NB	MM 0.001 LT	G	W1-7	48	24		↔	8.00								2		24.0 ~~30~~								INSTALL A NEW LARGE DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 164' NORTH OF POLE # 181	X		
NB	MM 0.001 LT	G	W2-4	30	30		T						~~X~~ 3		X											REMOVE THE EXISTING T INTERSECTION SIGN AND POST LOCATED 164' NORTH OF POLE # 181			
NB	MM 0.002 LT	G H	D3-1	66	12		Swinington Hill Rd	5.50					X		X	2		26.5 ~~30~~								REPLACE THE EXISTING STREET NAME SIGN ON TWO NEW POSTS LOCATED 158' NORTH OF POLE # 181		15	
NB	MM 0.006 LT	F	R1-1	30	30		STOP	6.25					X		X	1		12.5 ~~15~~								REPLACE EXISTING STOP SIGN AND POST LOCATED 137' NORTH OF POLE # 181	X		
SB	MM 0.020 RT	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		13.25 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 63' NORTH OF AND ACROSS FROM POLE # 181	X		
NB	MM 0.034 LT	F	D1-1	72	12		↑ Leicester 2	6.00								2		23.5 ~~30~~								INSTALL A NEW D-BOARD SIGN ON TWO NEW POSTS LOCATED 11' SOUTH OF POLE # 181		17	
NB	MM 0.034 LT	F	D1-1	72	12		← Whiting 4	6.00																		INSTALL A NEW D-BOARD SIGN BENEATH AND ON THE SAME POSTS AS THE NEW D1-1 SIGN LOCATED 11' SOUTH OF POLE # 181		18	
SB	MM 0.058 RT	A	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 11' NORTH OF POLE # 223/44			
										EA	EA	EA	EA ~~6~~ 8	EA	EA 6		FT	FT ~~195~~ 163.75	FT		LB	LB	LB	LB					
								SF 53.25	SF	EA ~~6~~ 8				EA 6		EA 13	FT ~~195~~ 163.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PLOT DATE: 12/20/2013
PROJECT LEADER: P. COBURN
DRAWN BY: N. PATTIS
DESIGNED BY: N. PATTIS
CHECKED BY: B. GROSE
LEICESTER TRAFFIC SIGN SUMMARY SHEET 8
SHEET 35 **OF** 87