STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

PITTSFORD
MEADOW LAKE DRIVE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
							CHITTENDEN ROAD																						
NB	MM 0.000 RT	C D	VD-024	72	10		Pittsford / Rutland Town			X				X												RETAIN EXISTING TOWN LINE SIGN AND POST LOCATED 60' NORTH OF POLE # 43/3/NET/3			
SB	MM 0.000 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		11.75 ~~15~~								REPLACE THE EXISTING SPEED LIMIT SIGN AND POST LOCATED 60' NORTH OF AND ACROSS FROM POLE # 43/3/NET/3	X		
NB	MM 0.007 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		13.25 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 121' SOUTH OF POLE # 2/2	X		
NB	MM 0.076 RT	A	W2-2	30	30			6.25								1		15.75 ~~15~~								INSTALL A NEW SIDE ROAD RIGHT SIGN AND POST LOCATED ADJACENT TO POLE # 43/1/35-3/1	X		
NB	MM 0.076 RT	A	W16-8P	26	15		Meadow Lake Dr	2.71																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW SIDE ROAD RIGHT SIGN LOCATED ADJACENT TO POLE # 43/1/35-3/1		16	
SB	MM 0.076 LT	F	S3-1	36	36	FYG		9.00								2		30.25 ~~30~~								INSTALL A NEW SCHOOL BUS STOP AHEAD SIGN ON TWO NEW POSTS LOCATED ACROSS FROM POLE # 43/1/35-3/1	X		
SB	MM 0.091 LT	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						X		X											REMOVE EXISTING SCHOOL BUS STOP AHEAD SIGN AND POST LOCATED 79' NORTH OF AND ACROSS FROM POLE # 43/1/35-3/1			
SB	MM 0.127 LT	E F	D3-1	60	12		Meadow Lake Dr						X		X											REMOVE EXISTING STREET NAME SIGN AND POST LOCATED 26' NORTH OF POLE # 4/105/57			
SB	MM 0.127 LT	G H	D3-1	54	12		Chittenden Rd						X													REMOVE EXISTING STREET NAME SIGN LOCATED 26' NORTH OF POLE # 4/105/57			
SB	MM 0.127 LT	G	D1-1	72	10		Chittenden 1 →						X													REMOVE EXISTING D BOARD LOCATED 26' NORTH OF POLE # 4/105/57			
SB	MM 0.127 LT	G H	D3-1	60	12		East Pittsford Rd	5.00					X			2		22.25 ~~30~~								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 26' NORTH OF POLE # 4/105/57		13	
SB	MM 0.127 LT	G	W1-7	48	24		↔	8.00					X			2		23.75 ~~30~~								REPLACE THE EXISTING LARGE DOUBLE ARROW SIGN ON TWO NEW POSTS LOCATED 26' NORTH OF POLE # 4/105/57	X		
SB	MM 0.128 LT	G	R1-1	30	30		STOP						X		X											REMOVE EXISTING STOP SIGN AND POST LOCATED 32' NORTH OF POLE # 4/105/57			
NB	MM 0.173 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		12.25 ~~15~~								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 106' NORTH OF POLE # 4/106	X		
										EA 1	EA	EA	EA ~~7~~ 9	EA 1	EA 5		FT	FT ~~150~~ 129.25	FT		LB	LB	LB	LB				
								SF 45.96	SF	EA ~~8~~ 10				EA 6		EA 10		FT ~~150~~ 129.25		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE