STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

PITTSFORD
MEADOW LAKE DRIVE

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.187 LT	F	W2-2L	30	30			6.25								1		14.25 ~~15~~								INSTALL A NEW SIDE ROAD LEFT SIGN AND POST LOCATED 21' NORTH OF POLE # CV65T/4/107/59	X		
SB	MM 0.187 LT	F	W16-8P	26	15		Meadow Lake Dr	2.71																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2L SIGN LOCATED 21' NORTH OF POLE # CV65T/4/107/59		16	
NB	MM 0.555 RT	A	W1-2R	30	30			6.25								1		13.0 ~~15~~								INSTALL A NEW CURVE RIGHT SIGN AND POST LOCATED 21' NORTH OF POLE # 15T/35/71/119	X		
NB	MM 0.574 RT	C D	VD-024	72	10		Chittenden Pittsford	5.00					X		X	2		18.75 ~~30~~								REPLACE EXISTING TOWN LINE SIGN ON TWO NEW POSTS LOCATED 121' NORTH OF POLE # 15T/35/71/119		16	
SB	MM 0.574 LT	F	R2-1	24	30		SPEED LIMIT 35	5.00					X		X	1		13.75 ~~15~~								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 121' NORTH OF AND ACROSS FROM POLE # 15T/35/71/119	X		
NB	MM 0.575 RT	A	R2-1	24	30		SPEED LIMIT 35	5.00								1		10.75 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 127' NORTH OF POLE # 15T/35/71/119	X		
							MEADOW LAKE DRIVE																						
WB	MM 0.010 LT	G H	D3-1	60	12		Meadow Lake Dr	5.00								2		22.5 ~~30~~								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 53' EAST OF THE INTERSECTION OF EAST PITTSFORD ROAD AND MEADOW LAKE DRIVE		14	
WB	MM 0.010 RT	F	R1-1	30	30		STOP	6.25					X			1		13.75 ~~15~~								INSTALL A NEW STOP SIGN AND POST LOCATED 53' EAST OF THE INTERSECTION OF EAST PITTSFORD ROAD AND MEADOW LAKE DRIVE (MAY NEED TO DRILL HOLE IN LEDGE TO INSTALL POST)	X		
EB	MM 0.012 RT	B	R1-1	30	30		STOP NOT INSTALLED AS NO ROOM ON LEFT TO INSTALL	~~6.25~~								1		~~15~~								INSTALL A NEW STOP SIGN AND POST LOCATED 63' EAST OF THE INTERSECTION OF EAST PITTSFORD ROAD AND MEADOW LAKE DRIVE	X		
WB	MM 0.031 LT	F	D1-1	72	12		Chittenden 1 →	6.00								2		20.25 ~~30~~								INSTALL A NEW D-BOARD ON TWO NEW POSTS LOCATED 401' WEST OF AND ACROSS FROM MAILBOX # 85		17	
EB	MM 0.043 RT	A	R1-1	24	30		SPEED LIMIT 35	5.00								1		13.75 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 338' WEST OF MAILBOX # 85	X		
										EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB					
													~~2~~ 3		2			~~195~~ 140.75											
								SF	SF	EA				EA		EA	FT			EA	LB								
								~~58.71~~ 52.46					~~2~~ 3		2	13		~~195~~ 140.75											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE