STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 5

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 1.358 LT	F	W16-8P	48	15		Gulf Rd / Harrington Cross Rd	5.00																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POSTS AS THE NEW W2-7L SIGN LOCATED 53' WEST OF POLE # 2-6-36		16	
WB	MM 1.368 LT	F	VW-276	30	30		DRIFTING SNOW	6.25								1		15 (ASSUMED)								INSTALL A NEW DRIFTING SNOW SIGN AND POST LOCATED ACROSS FROM POLE # 2-6-36		12	
EB	MM 1.778 RT	A	W1-2L	30	30								~~2~~ *		X											REMOVE EXISTING LEFT CURVE SIGN AND POST LOCATED 729' WEST OF POLE # CTC/107/2-6-49			
EB	MM 1.809 RT	A	W1-3MA	36	36			9.00								2		30								INSTALL A NEW REVERSE TURN, SIDEROAD SIGN ON TWO NEW POSTS LOCATED 565' WEST OF POLE # CTC/107/2-6-49		13	
EB	MM 1.809 RT	A	W16-8P	36	8		North End Rd	2.00																		INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-3MA SIGN LOCATED 565' WEST OF POLE # CTC/107/2-6-49		17	
EB	MM 1.809 RT	A	W13-1P	18	18		30 M.P.H.	2.25																		INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W16-8P SIGN LOCATED 565' WEST OF POLE # CTC/107/2-6-49	X		
EB	MM 1.876 RT	A	W1-2R	30	30								X		X											REMOVE EXISTING RIGHT CURVE SIGN AND POST LOCATED 211' WEST OF POLE # CTC/107/2-6-49			
EB	MM 1.876 RT	A	W13-1P	18	18		30 M.P.H.						X													REMOVE EXISTING ADVISORY SPEED PLAQUE LOCATED 211' WEST OF POLE # CTC/107/2-6-49			
WB	MM 1.946 LT	F	W1-6L	48	24			8.00								2		23.25 ~~30~~								INSTALL A NEW LARGE LEFT ARROW SIGN ON TWO NEW POSTS LOCATED ADJACENT TO POLE # CTC/6/1	X		
WB	MM 1.947 LT	H	R1-1	30	30		STOP	6.25					X		X	1		12.25 ~~15~~								REPLACE EXISTING STOP SIGN AND POST LOCATED 5' EAST OF POLE # CTC/6/1	X		
WB	MM 1.957 LT	E F	D3-1	42	12		North End Rd	3.50					X		X	1		10.0 ~~15~~								REPLACE THE EXISTING STREET NAME SIGN AND POST LOCATED ADJACENT TO POLE # 9/93/2-6-2-1		15	
WB	MM 1.957 LT	E	W1-6R	48	24			8.00								2		23.0 ~~30~~								INSTALL A NEW LARGE RIGHT ARROW SIGN ON TWO NEW POSTS LOCATED ADJACENT TO POLE # 9/93/2-6-2-1	X		
WB	MM 1.965 LT	E	W1-6R	48	24								X		X											REMOVE EXISTING LARGE RIGHT ARROW SIGN AND POST LOCATED 42' EAST OF POLE # 9/93/2-6-2-1			
										EA	EA	EA	EA ~~6~~ 7	EA	EA 5		FT	FT ~~135~~ 113.5	FT		LB	LB	LB	LB					
								SF 50.25	SF	EA ~~6~~ 7				EA 5		EA 9	FT ~~135~~ 113.5			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
TINMOUTH TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 49 **OF** 87