STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 2.001 LT	A	W1-3MB	36	36			9.00								2		27.5 ~~30~~									INSTALL A NEW REVERSE TURN, SIDEROAD SIGN ON TWO NEW POSTS LOCATED 16' WEST OF POLE # CTC/6/105/93/92/2-6-51		13	
WB	MM 2.001 LT	A	W16-8P	36	8			2.00																			INSTALL A NEW STREET NAME PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-3MB SIGN LOCATED 16' WEST OF POLE # CTC/6/105/93/92/2-6-51		17	
WB	MM 2.001 LT	A	W13-1P	18	18			2.25																			INSTALL A NEW SPEED LIMIT PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W16-8P SIGN LOCATED 16' WEST OF POLE # CTC/6/105/93/92/2-6-51	X		
WB	MM 2.036 LT	F	W1-3L	30	30								X		X												REMOVE EXISTING REVERSE TURN LEFT SIGN AND POST LOCATED 63' WEST OF AND ACROSS FROM POLE # VTEL/104/91/2-6-52			
WB	MM 2.050 LT	F	W1-5L	36	36			9.00								2		30									INSTALL A NEW WINDING ROAD SIGN ON TWO NEW POSTS LOCATED 11' NORTH OF AND ACROSS FROM POLE # VTEL/104/91/2-6-52	X		
WB	MM 2.050 LT	F	W7-3aP	24	18			3.00																			INSTALL A NEW NEXT 1 MILE SIGN BENEATH AND ON THE SAME POST AS THE NEW W1-5L SIGN LOCATED 11' NORTH OF AND ACROSS FROM POLE # VTEL/104/91/2-6-52	X		
WB	MM 2.050 LT	F	W13-1P	18	18			2.25																			INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W1-5L	X		
EB	MM 2.950 RT	A	R2-5	24	30								X		X												REMOVE THE EXISTING REDUCED SPEED AHEAD SIGN AND POST LOCATED 63' WEST OF POLE # CTC/88/93/75			
EB	MM 2.950 RT	A	W3-5	36	36			9.00								2		27.5 ~~30~~									INSTALL A NEW 25 MPH AHEAD SIGN ON TWO NEW POSTS LOCATED 63' WEST OF POLE # CTC/88/93/75	X		
EB	MM 3.036 RT	A	R2-1	24	30			5.00					X		X	1		12.25 ~~15~~									REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 153' WEST OF AND ACROSS FROM POLE # CTC/86/73	X		
WB	MM 3.036 LT	F	TOWN SIGN	24	30								X		X												REMOVE EXISTING END SPEED ZONE SIGN AND POST LOCATED 153' WEST OF POLE # CTC/86/73			
WB	MM 3.036 LT	F	R2-1	24	30			5.00								1		12.25 ~~15~~									INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 153' WEST OF POLE # CTC/86/73	X		
								SF 46.5	SF	EA 4				EA 4		EA 8		FT ~~120~~ 109.50		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn **PLOT DATE:** 12/20/2013
PROJECT LEADER: P. COBURN **DRAWN BY:** N. PATTIS
DESIGNED BY: N. PATTIS **CHECKED BY:** B. GROSE
TINMOUTH TRAFFIC SIGN SUMMARY SHEET 6 **SHEET** 50 **OF** 87