STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM 3.093 RT	A	TOWN SIGN	36	36		SCHOOL ZONE						X		X												REMOVE EXISTING SCHOOL ZONE SIGN AND POST LOCATED 148' EAST OF AND ACROSS FROM POLE # CTC/86/73			
EB	MM 3.093 RT	A	S1-1	36	36								X														REMOVE EXISTING SCHOOL SIGN LOCATED 148' EAST OF AND ACROSS FROM POLE # CTC/86/73			
EB	MM 3.093 RT	A	S1-1	36	36	FYG		9.00								2		22.0 ~~30~~									INSTALL A NEW SCHOOL SIGN ON TWO NEW POSTS LOCATED 148' EAST OF AND ACROSS FROM POLE # CTC/86/73	X		
EB	MM 3.093 RT	A	W16-9P	24	12	FYG	AHEAD	2.00																			INSTALL A NEW AHEAD PLAQUE BENEATH THE NEW S1-1 SIGN LOCATED 148' EAST OF AND ACROSS FROM POLE # CTC/86/73	X		
EB	MM 3.138 RT	A	W1-1L	30	30								~~2~~ X		X												REMOVE EXISTING TURN LEFT SIGN AND POST LOCATED 306' WEST OF AND ACROSS FROM POLE # 70/A			
EB	MM 3.196 RT	A	D1-1	72	12		Wallingford 5	6.00								2		23.5 ~~30~~									INSTALL A NEW D-BOARD SIGN ON TWO NEW POSTS LOCATED ACROSS FROM POLE # 70/A		18	
EB	MM 3.232 RT	A	W1-1ML	36	36								X		X												REMOVE EXISTING TURN LEFT, SIDEROAD SIGN AND POST LOCATED ADJACENT TO POLE # CTC-VT/82			
EB	MM 3.232 RT	A	M3-2	24	12		EAST	2.00								1		14.25 ~~15~~									INSTALL A NEW EAST CARDINAL DIRECTION SIGN AND POST LOCATED ADJACENT TO POLE # CTC-VT/82			E-136C
EB	MM 3.232 RT	A	M1-6	30	24		140	5.00																			INSTALL A NEW ROUTE 140 SIGN BENEATH AND ON THE SAME POST AS THE NEW M3-2 SIGN LOCATED ADJACENT TO POLE # CTC-VT/82			E-136C
EB	MM 3.232 RT	A	M6-1	21	15			2.19																			INSTALL A NEW LEFT ARROW SIGN BENEATH AND ON THE SAME POST AS THE NEW M1-5 SIGN LOCATED ADJACENT TO POLE # CTC-VT/82			E-136C
EB	MM 3.251 RT	A	TOWN SIGN				Tinmouth Pond						X		X												REMOVE EXISTING D-BOARD SIGN AND POST LOCATED 148' WEST OF AND ACROSS FROM POLE # CTC/80/93/67			
EB	MM 3.251 RT	A	TOWN SIGN				Wallingford 5						X														REMOVE EXISTING D-BOARD SIGN LOCATED 148' WEST OF AND ACROSS FROM POLE # CTC/80/93/67			
EB	MM 3.251 RT	A	M3-2	24	12		EAST						X														REMOVE EXISTING EAST CARDINAL DIRECTION SIGN LOCATED 148' WEST OF AND ACROSS FROM POLE # CTC/80/93/67			
EB	MM 3.251 RT	A	M1-5	30	24		140						X														REMOVE EXISTING ROUTE 140 SIGN LOCATED 148' WEST OF AND ACROSS FROM POLE # CTC/80/93/67			
								SF 26.19	SF	EA ~~8~~ 9	EA	EA	EA ~~8~~ 9	EA 4	EA 4	EA 5	FT ~~75~~ 59.75	FT ~~75~~ 59.75	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn **PLOT DATE:** 12/20/2013
PROJECT LEADER: P. COBURN **DRAWN BY:** N. PATTIS
DESIGNED BY: N. PATTIS **CHECKED BY:** B. GROSE
TINMOUTH TRAFFIC SIGN SUMMARY SHEET 7 **SHEET** 51 **OF** 87