STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 4.429 RT	A	R1-1	30	30		STOP	6.25								1		13.75 ~~15~~								INSTALL A NEW STOP SIGN AND POST LOCATED 259' EAST OF AND ACROSS FROM POLE # 50T/CTC/58/93/52	X		
WB	MM 4.429 LT	F	R1-1	30	30		STOP	6.25								1		14.0 ~~15~~								INSTALL A NEW STOP SIGN AND POST LOCATED 259' EAST OF POLE # 50T/CTC/58/93/52	X		
EB	MM 4.429 RT	D	R1-1	30	30		STOP						X		X											REMOVE EXISTING STOP SIGN AND POST LOCATED 259' EAST OF AND ACROSS FROM POLE # 50T/CTC/58/93/52			
EB	MM 4.429 RT	C	M1-6	30	24		140						X		X											REMOVE EXISTING ROUTE 140 SIGN AND POST LOCATED 259' EAST OF AND ACROSS FROM OPLE # 50T/CTC/58/93/52			
EB	MM 4.429 RT	C	M5-1R	21	15								X													REMOVE EXISTING RIGHT ARROW SIGN LOCATED 259' EAST OF AND ACROSS FROM POLE # 50T/CTC/58/93/52			
EB	MM 4.429 RT	C	R2-1	24	30		SPEED LIMIT 45	5.00					X			1		14.0 ~~15~~								REPLACE EXISTING SPEED LIMIT SIGN AND POST LOCATED 259' EAST OF AND ACROSS FROM POLE # 50T/CTC/58/93/52	X		
EB	MM 4.439 RT	A	W2-2L	30	30			6.25								1		15.25 ~~15~~								INSTALL A NEW INTERSECTION LEFT SIGN AND POST LOCATED 300' SOUTH OF THE INTERSECTION OF EAST ROAD AND ROUTE 140 ON EAST ROAD	X		
EB	MM 4.439 RT	A	W13-1P	18	18		25 M.P.H.	2.25																		INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE NEW W2-2L SIGN LOCATED 300' SOUTH OF THE INTERSECTION OF EAST ROAD AND ROUTE 140	X		
EB	MM 4.439 RT	A	R1-1	30	30		STOP						2 ~~X~~		X											REMOVE THE EXISTING STOP SIGN AND POST LOCATED 16' WEST OF POLE # CTC/57/93/51			
EB	MM 4.440 RT	C	D3-1	30	12		East Rd	2.50								1		11.5 ~~15~~								INSTALL A NEW STREET NAME SIGN AND POST LOCATED 11' WEST OF POLE # CTC/57/93/51		13	
EB	MM 4.440 RT	C	M1-6	30	24		140						X		X											REMOVE EXISTING ROUTE 140 SIGN AND POST LOCATED 11' WEST OF POLE # CTC/57/93/51			
EB	MM 4.440 RT	C	M6-1L	21	15								X													REMOVE EXISTING LEFT ARROW SIGN LOCATED 11' WEST OF POLE # CTC/57/93/51			
										EA	EA	EA	EA ~~7~~ 8	EA	EA 4		FT	FT ~~75~~ 68.50	FT		LB	LB	LB	LB					
								SF 28.50	SF	EA ~~7~~ 8				EA 4		EA 5	FT ~~75~~ 68.50			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
TINMOUTH TRAFFIC SIGN SUMMARY SHEET II

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 55 **OF** 87