STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 4.516 LT	F	W1-1MbR	30	30								X		X												REMOVE EXISTING TURN RIGHT, INTERSECTION SIGN AND POST LOCATED 26' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56			
WB	MM 4.516 LT	F	TOWN SIGN	30	30								X														REMOVE EXISTING DANGEROUS INTERSECTION SIGN LOCATED 26' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56			
WB	MM 4.516 LT	F	W2-2R	30	30			6.25								1		13.5 ~~15~~									INSTALL A NEW SIDE ROAD RIGHT SIGN AND POST LOCATED 26' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56	X		
WB	MM 4.516 LT	F	W13-1P	18	18			2.25																		INSTALL A NEW ADVISORY SPEED PLAQUE BENEATH AND ON THE SAME POST AS THE NEW INTERSECTION RIGHT SIGN LOCATED 26' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56	X		
WB	MM 4.536 LT	F	R1-2	36	36			4.50					X		X	1		13.25 ~~15~~									REPLACE THE EXISTING YIELD SIGN AND POST LOCATED 132' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56	X		
WB	MM 4.542 LT	E	D3-1	54	12								X		X												REMOVE EXISTING STREET NAME SIGN AND POST LOCATED 164' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56			
WB	MM 4.542 LT	E	M1-6	30	24								X														REMOVE EXISTING ROUTE 140 SIGN LOCATED 164' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56			
WB	MM 4.542 LT	E	M6-1R	21	15								X														REMOVE EXISTING RIGHT ARROW LOCATED 164' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56			
WB	MM 4.546 LT	E	W1-6R	48	24			8.00								2		26.0 ~~30~~									INSTALL A NEW LARGE RIGHT ARROW SIGN ON TWO NEW POSTS LOCATED 185' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56	X		
WB	MM 4.546 LT	F	W1-6L	48	24			8.00								2		27.0 ~~30~~									INSTALL A NEW LARGE LEFT ARROW SIGN ON TWO NEW POSTS LOCATED 185' EAST OF AND ACROSS FROM POLE # 93/50/CTC/56	X		
WB	MM 4.546 LT	F	M1-6	30	24								X		X												REMOVE EXISTING ROUTE 140 SIGN AND POST LOCATED ADJACENT TO POLE # 93/49/CTC/6/55			
WB	MM 4.546 LT	F	M6-1L	21	15								X														REMOVE EXISTING LEFT ARROW SIGN AND POST LOCATED ADJACENT TO POLE # 93/49/CTC/6/55			
								SF 29.00	SF	EA 8			EA 8	EA 4	EA 4	EA 6	FT ~~90~~ 79.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME:	STATEWIDE SOUTHWEST REGION
PROJECT NUMBER:	STP HRRR(19)
FILE NAME: 13k036wrk.dgn	PLOT DATE: 12/20/2013
PROJECT LEADER: P. COBURN	DRAWN BY: N. PATTIS
DESIGNED BY: N. PATTIS	CHECKED BY: B. GROSE
TINMOUTH TRAFFIC SIGN SUMMARY SHEET 13	SHEET 57 OF 87