STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 17

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 5.900 RT	A	W1-2L	30	30								X		X											REMOVE EXISTING CURVE LEFT SIGN AND POST LOCATED 174' EAST OF POLE # VTEL/26			
EB	MM 5.919 RT	A	OM1-1	18	18								X		X											REMOVE THE EXISTING OBJECT MARKER SIGN AND POST LOCATED 275' EAST OF POLE # VTEL/26			
EB	MM 5.925 RT	C	VD-024	72	10		Wallingford Tinmouth	5.00								2		21.25 ~~30~~								INSTALL A NEW TOWN LINE SIGN ON TWO NEW POSTS LOCATED 306' EAST OF POLE # VTEL/26		16	
							MOUNTAIN VIEW ROAD																						
SB	MM 0.000 RT	C D	D3-1	66	12		Mountain View Rd	5.50								2		20.25 ~~30~~								INSTALL A NEW STREET NAME SIGN ON TWO NEW POSTS LOCATED 211' NORTH OF POLE # 933/1/CTC/30		14	
SB	MM 0.000 RT	A B	D3-1	30	12		Bliss Rd	2.50					X		X	1		11.0 ~~15~~								REPLACE EXISTING STREET NAME SIGN AND POST LOCATED 211' NORTH OF POLE # 933/1/CTC/30		13	
NB	MM 0.018 LT	F	D1-1	72	12		↑ Middletown Springs 5	6.00								2		26.0 ~~30~~								INSTALL A NEW D-BOARD SIGN ON TWO NEW POSTS LOCATED 116' NORTH OF AND ACROSS FROM POLE # 933/1/CTC/30		17	
NB	MM 0.018 LT	F	D1-1	72	12		Wallingford 5 →	6.00																		INSTALL A NEW D-BOARD SIGN BENEATH AND ON THE SAME POST AS THE NEW D1-1 SIGN LOCATED 116' NORTH OF AND ACROSS FROM POLE # 933/1/CTC/30		18	
NB	MM 0.018 LT	F	D1-1	72	12		↑ West Rutland 12	6.00																		INSTALL A NEW D-BOARD SIGN BENEATH AND ON THE SAME POST AS THE NEW D1-1 SIGN LOCATED 116' NORTH OF AND ACROSS FROM POLE # 933/1/CTC/30		18	
SB	MM 0.024 RT	A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						X		X											REMOVE THE EXISTING LEGAL LOAD LIMIT SIGN AND POST LOCATED 84' NORTH OF POLE # 933/1/CTC/30			
NB	MM 0.045 LT	F	M2-1	21	15		JCT	2.19								1		13.25 ~~15~~								INSTALL A NEW JCT SIGN AND POST LOCATED 26' SOUTH OF AND ACROSS FROM POLE # 933/1/CTC/30			E-136C
NB	MM 0.045 LT	F	M1-6	30	24		140	5.00																		INSTALL A NEW ROUTE 140 SIGN BENEATH AND ON THE SAME POST AS THE NEW M2-1 SIGN LOCATED 26' SOUTH OF AND ACROSS FROM POLE # 933/1/CTC/30			E-136C
										EA	EA	EA	EA 4	EA	EA 4		FT	FT ~~120~~ 91.75	FT		LB	LB	LB	LB					
								SF 38.19	SF	EA 4				EA 4		EA 8	FT ~~120~~ 91.75			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
TINMOUTH TRAFFIC SIGN SUMMARY SHEET 17

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 61 OF 87