STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 18

TINMOUTH
SNTH 140

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.083 LT	F	S1-1	36	36	FYG		9.00								2		26.0 ~~30~~								INSTALL A NEW SCHOOL SYMBOL SIGN ON TWO NEW POSTS LOCATED 227' SOUTH OF AND ACROSS FROM POLE # 933/1/CTC/30	X		
NB	MM 0.083 LT	F	W16-9P	24	12	FYG	AHEAD	2.00																		INSTALL A NEW AHEAD PLAQUE BENEATH AND ON THE SAME POST AS THE NEW S1-1 SIGN LOCATED 227' SOUTH OF AND ACROSS FROM POLE # 933/1/CTC/30	X		
NB	MM 0.096 LT	F	W3-1	30	30								X		X											REMOVE EXISTING STOP AHEAD SIGN AND POST LOCATED 201' NORTH OF MAILBOX # 34			
SB	MM 0.127 RT	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		12.0 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 37' NORTH OF AND ACROSS FROM MAILBOX # 34	X		
NB	MM 0.127 LT	F	TOWN SIGN	30	30		SLOW SCHOOL ZONE						X		X											REMOVE EXISTING SLOW SCHOOL ZONE SIGN AND POST LOCATED 37' NORTH OF MAILBOX # 34			
NB	MM 0.127 LT	F	R2-1	24	30		SPEED LIMIT 25	5.00								1		13.5 ~~15~~								INSTALL A NEW SPEED LIMIT SIGN AND POST LOCATED 37' NORTH OF MAILBOX # 34	X		
SB	MM 0.177 RT	A	R2-1	24	30		SPEED LIMIT 40						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 116' NORTH OF AND ACROSS FROM POLE # 933/4A/63/33-1			
NB	MM 0.177 LT	F	R2-1	24	30		SPEED LIMIT 25						X		X											REMOVE EXISTING SPEED LIMIT SIGN AND POST LOCATED 116' NORTH OF POLE # 933/4A/63/33-1			
NB	MM 0.220 LT	F	W3-1	36	36			9.00								2		32.75 ~~30~~								INSTALL A NEW 25 MPH AHEAD SIGN ON TWO NEW POSTS LOCATED 32' SOUTH OF POLE # 933/4A/63/33-1	X		
NB	MM 0.282 LT	F	R2-5	24	30		REDUCED SPEED AHEAD						X		X											REMOVE THE EXISTING REDUCED SPEED AHEAD SIGN AND POST LOCATED 359' SOUTH OF POLE # 933/4A/63/33-1			
										EA	EA	EA	EA 5	EA	EA 5		FT	FT ~~90~~ 84.25	FT		LB	LB	LB	LB					
								SF 30.00	SF	EA 5				EA 5		EA 6	FT ~~90~~ 84.25			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHWEST REGION
PROJECT NUMBER: STP HRRR(19)

FILE NAME: 13k036wrk.dgn
PROJECT LEADER: P. COBURN
DESIGNED BY: N. PATTIS
TINMOUTH TRAFFIC SIGN SUMMARY SHEET 18

PLOT DATE: 12/20/2013
DRAWN BY: N. PATTIS
CHECKED BY: B. GROSE
SHEET 62 **OF** 87